

AD-A101 988


ARMY ENGINEER DISTRICT PHILADELPHIA PA
FLOOD PLAIN INFORMATION, SHABAKUNK CREEK, WEST BRANCH SHABAKUNK--ETC(U)
OCT 73
DAEN/NAP-82040/FPI90-73/1

F/G 8/8

UNCLASSIFIED

NL

1 of 2
AD-A
10 810



~~LEVEL~~
**FLOOD PLAIN
INFORMATION**

①
B.S.

SHABAKUNK CREEK

**WEST BRANCH SHABAKUNK AND
LITTLE SHABAKUNK CREEKS
MERCER COUNTY, NEW JERSEY**

AD A 1 3 1 0 0 0



DTIC

JUL 24 1981

DTIC FILE COPY

PREPARED FOR THE MERCER COUNTY PLANNING BOARD AND THE NEW JERSEY
DEPARTMENT OF ENVIRONMENTAL PROTECTION BY THE DEPT. OF THE ARMY,
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS, PHILADELPHIA, PA.

REPT NO: DAEN/NAP-82040/FPI40-73/10

*Original contains color
plates: All DTIC reproduct-
ions will be in black and
OCTOBER 1973

81 7 24 108 8

This folder is an announcement of and supplement to the "Flood Plain Information (FPI) Report, Shabakunk Creek, West Branch Shabakunk Creek, and Little Shabakunk Creek, Mercer County, New Jersey." The report has been prepared to emphasize the importance of flood potential and flood hazards in land use planning and to

FLOODS

FLOODS

on SHABAKUNK CREEK,

WEST BRANCH SHABAKUNK CREEK AND

LITTLE SHABAKUNK CREEK

Inside are sketches illustrating the horizontal and vertical relationships of flooded areas and a flood area map from the report showing the extent of the Floodway Design Flood (FDF), Flood Hazard Area Design Flood (FHADF), and the Standard Project Flood (SPF) in a portion of the study area.

This folder has been prepared for the Mercer County Planning Board by the U.S. Army Corps of Engineers from data in the report "Flood Plain Information, Shabakunk Creek, West Branch Shabakunk Creek, and Little Shabakunk Creek, Mercer County, New Jersey." Copies of the report and this folder are available upon request from the Mercer County Planning Board, P.O. Box 1777, Trenton, New Jersey 08607.



is needed

Shabakunk Creek, West Creek and Little Shabakunk Creek are extensively developed. Industrial and commercial development is presently and can increase in the future. The extent of flooding will be even more extensive if action is taken.

Measures such as zoning and building codes can be adopted to reduce increased flood damage. Flood plain information can reduce potential damage to areas already subject to flooding. Additional works to modify the flood plain are a part of the long-run plan.

Along Shabakunk Creek, West Branch Shabakunk Creek, and Little Shabakunk Creek are not the only ones affected. Flood plain information has been provided for 1,360 flood-plagued areas. 600 of those having flood plain information in 1972 have adopted or are adopting flood plain information, while 760 others have not. A total of 1,360 flood-plagued areas have been identified in the FPI Reports in Mercer County.

Location	Flood of	Aug. 28-29, 1971	(100-yr.)	Flood Design Hazard Area	N.J. Floodway	N.J. Floodway Design Hazard Area
Green Lane	84.1	83.3	83.9	83.9	83.9	83.9
Ewingville Rd.	97.3	94.2	95.0	95.0	95.0	95.0
Bull Run Rd.	113.2	112.1	112.1	112.1	112.1	112.1

PAST AND POSSIBLE FUTURE FLOOD HEIGHTS ON SHABAKUNK CREEK
Elevation—Feet, Mean Sea Level Datum

PAST AND POSSIBLE FUTURE FLOOD HEIGHTS ON SHABAKUNK CREEK

Elevation—Feet, Mean Sea Level Datum		Location	
85.9	Standard Project Flood	Green Lane	84.1
83.9	Hazard Area Design Flood		Aug. 28-29, 1971
83.3	N.J. Flood		
	Floodway Design Flood		
	(100-Yr.)		

ACTION is needed


The flood plains of Shabakunk Creek, West Branch Shabakunk Creek and Little Shabakunk Creek are extensively developed. Additional residential and commercial development is occurring presently and can be expected to increase in the future. The devastating effects of flooding will be even greater unless action is taken.

Effective regulatory measures such as zoning ordinances and building codes can be designed to prevent increased flood damages. Flood proofing can reduce potential damages to properties already subject to flooding, and additional works to modify flooding can also be a part of the long-run solution.

The communities along Shabakunk Creek, West Branch Shabakunk Creek, and Little Shabakunk Creek are not the only ones with flooding problems. Flood plain information has already been provided for many of several thousand flood-plagued communities. Nearly 600 of those having FPI Reports by mid 1972 have adopted or strengthened regulations, while 760 others have them under study. A total of 1,360 communities have used the FPI Reports in planning land use control.

Inside are sketches illustrating the horizontal and vertical relationships of flooded areas and a flood area map from the report showing the extent of the Floodway Design Flood (FDF), Flood Hazard Area Design Flood (FHADF), and the Standard Project Flood (SPF) in a portion of the study area.

This folder has been prepared for the Mercer County Planning Board by the U.S. Army Corps of Engineers from data in the report "Flood Plain Information, Shabakunk Creek, West Branch Shabakunk Creek, and Little Shabakunk Creek, Mercer County, New Jersey." Copies of the report and this folder are available upon request from the Mercer County Planning Board, P.O. Box 1777, Trenton, New Jersey 08607.



FLOODS FLOODS FLOODS ON SHABAKUNK CREEK,

This folder is an announcement of and supplement to the "Flood Plain Information (FPI) Report, Shabakunk Creek, West Branch Shabakunk Creek, and Little Shabakunk Creek, Mercer County, New Jersey." The report has been prepared to emphasize the importance of flood potential and flood hazards in land use planning and to aid in management decisions concerning flood plain utilization.

Although Ewing Township, Lawrence Township, and other communities along Shabakunk, West Branch Shabakunk, and Little Shabakunk Creeks have suffered extensive damage from past floods, studies indicate that even larger floods can occur in the future. Emphasis is given to future floods in the FPI Report. Maps, profiles, and cross sections have been included to illustrate the possible extent and severity of future floods.

Included in this folder are photographs showing possible future flood heights at selected locations. The flood height shown for a large flood, the New Jersey Floodway Design Flood (NJFDF), is one that occurs once in 100 years on the average, although it could occur in any year. Also indicated is the flood height that would be reached if a very large, Standard Project Flood (SPF), should occur. The Standard Project Flood represents a reasonable upper limit of expected flooding in the study area.


Inside are sketches illustrating the horizontal and vertical relationships of flooded areas and a flood area map from the report showing the extent of the Floodway Design Flood (FDF), Flood Hazard Area Design Flood (FHADF), and the Standard Project Flood (SPF) in a portion of the study area.

needed
Shabakunk Creek, West
and Little Shab-
commercial de-
ely developed.

PAST AND POSSIBLE FUTURE FLOOD HEIGHTS SHABAKUNK CREEK

Elevation—Feet, Mean Sea Level Datum

Location	Flood of Aug. 28-29, 1971	N.J. Floodway Design Flood (100-Yr.)
Green Lane	84.1	83.3
Ewingville Rd.	97.3	94.2
Bull Run Rd.	113.2	112.1



Future flood heights on West Branch Shabakunk Creek near Parkside Ave.



West branch
and Artie P

This folder has been prepared for the Mercer County Planning Board by the U.S. Army Corps

Inside are sketches illustrating the horizontal and vertical relationships of flooded areas and a flood area map from the report showing the extent of the Floodway Design Flood (FDF), Flood Hazard Area Design Flood (FHADF), and the Standard Project Flood (SPF) in a portion of the study area.


The flood plains of Shabakunk Creek, West Branch Shabakunk Creek and Little Shabakunk Creek are extensively developed. Additional residential and commercial development is occurring presently and can be expected to increase in the future. The

ACTION is needed

PAST AND POSSIBLE FUTURE FLOOD HEIGHTS ON SHABAKUNK CREEK

Elevation—Feet, Mean Sea Level Datum

Location	Flood of Aug. 28-29, 1971	N.J. Floodway Design Flood (100-Yr.)	N.J. Flood Hazard Area Design Flood	Standard Project Flood
Green Lane	84.1	83.3	83.9	85.9
Ewingville Rd.	97.3	94.2	95.0	97.7
Bull Run Rd.	113.2	112.1	113.0	114.4




Future flood heights on West Branch Shabakunk Creek near Parkside Ave.





West branch Shabakunk Creek at Oiden Ave. and Artye Parkway looking downstream



**BUILDING
in the
FLOOD PLAIN
can make
FLOODS
WIDER
and
DEEPER**




**normal
stream**




flood



**same flood
with build-up**



TOOLS of FLOOD PLAIN MANAGEMENT for the reduction of Flood Damage




**MEASURES TO REDUCE VULNERABILITY
TO FLOODS** provide for a future with more freedom
from flood damage, often at minor cost and with little
adverse effect on the environment


REGULATIONS

- (ZONING, BUILDING CODES, SUBDIVISION)
- FLOOD PROOFING • RELOCATIONS •
- URBAN RENEWAL •


MEASURES TO MODIFY FLOODS
are often required to alleviate existing problems and
sometimes to forestall future problems . . .




**DAMS &
RESERVOIRS**




**CHANNEL
ENLARGEMENT**






**HIGH FLOW
DIVERSION**



LEVEES



this
ENCROACHMENT
can change
a
Small Flood
into a
MAJOR FLOOD







FLOOD PLAIN MANAGEMENT for the reduction of Flood Damage and Human Suffering




REDUCE VULNERABILITY
for a future with more freedom
at minor cost and with little
environment
REGULATIONS
(ZONING CODES, SUBDIVISION)
RELOCATIONS
RENEWAL

MEASURES TO MODIFY FLOODS
are often required to alleviate existing problems and
sometimes to forestall future problems . . .



OTHER MEASURES
aid the Flood Plain
occupant in coping
with floods . . .

- EDUCATION**
- TAX ADJUSTMENTS**
- FLOOD INSURANCE**
- WARNING & EMERGENCY PLANS**




MEASURES TO REDUCE VULNERABILITY TO FLOODS provide for a future with more freedom from flood damage, often at minor cost and with little adverse effect on the environment


REGULATIONS

- (ZONING, BUILDING CODES, SUBDIVISION)
- FLOOD PROOFING • RELOCATIONS •
- URBAN RENEWAL •


MEASURES TO MODIFY FLOODS are often required to alleviate existing problems and sometimes to forestall future problems . . .




DAMS & RESERVOIRS




CHANNEL ENLARGEMENT



HIGH FLOW DIVERSION



LEVEES



FLOOD
FOR
NEW


LEG
app
of o

NO
N.
DE
STA
FLO


PROF
Flood
show
these
for th

MEASURES TO MODIFY FLOODS


are often required to alleviate existing problems and sometimes to forestall future problems . . .




**DAMS &
RESERVOIRS**



**CHANNEL
ENLARGEMENT**



**HIGH FLOW
DIVERSION**



LEVEES

OTHER

MEASURES
aid the Flood Plain
occupant in coping
with floods . . .

EDUCATION


**TAX
ADJUSTMENTS**

**FLOOD
INSURANCE**

**WARNING &
EMERGENCY
PLANS**

VULNERABILITY
more freedom
and with little
. . . .

**DIVISION)
ATIONS .**



**FLOOD PATTERNS
FOR SHABAKUNK CREEK
NEW JERSEY**

LEGEND

approximate limits
of overflow

NORMAL STREAM

**N. J. FLOODWAY
DESIGN FLOOD (NJFDF)**

**STANDARD PROJECT
FLOOD (SPF)**

**PROFILES in the
Flood Plain Information Report
show elevations of
these floods
for the entire study area**

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM	
1. REPORT NUMBER DAEN/NAP-82040/FPI40-73/10	2. GOVT ACCESSION NO. AD-A191 988	3. RECIPIENT'S CATALOG NUMBER	
4. TITLE (and Subtitle) Flood plain information, Shabakunk Creek, West Branch Shabakunk and Little Shabakunk Creeks, Mercer County, New Jersey		5. TYPE OF REPORT & PERIOD COVERED Flood plain information	
7. AUTHOR(s)		6. PERFORMING ORG. REPORT NUMBER DAEN/NAP-82040/FPI40-73/10	
9. PERFORMING ORGANIZATION NAME AND ADDRESS U.S. Army Engineer District Philadelphia 2nd & Chestnut Sts. Philadelphia, PA 19106		8. CONTRACT OR GRANT NUMBER(s)	
11. CONTROLLING OFFICE NAME AND ADDRESS U.S. Army Engineer District Philadelphia 2nd & Chestnut Sts. Philadelphia, PA 19106		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS	
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office)		12. REPORT DATE Oct. 1973	
		13. NUMBER OF PAGES 65	
		15. SECURITY CLASS. (of this report) UNCLASSIFIED	
16. DISTRIBUTION STATEMENT (of this Report) APPROVED FOR PUBLIC RELEASE; DISTRIBUTION UNLIMITED.		15a. DECLASSIFICATION/DOWNGRADING SCHEDULE	
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)			
18. SUPPLEMENTARY NOTES			
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Shabakunk Creek, NJ Mercer County, NJ Little Shabakunk Creek, NJ Mercer County Planning Board N.J. Dept. of Environmental Protection Floods Flood forecasting Flood plains			
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) The portion of Mercer County covered by this report is subject to flooding by Shabakunk Creek, West Branch Shabakunk Creek and Little Shabakunk Creek all of which are tributaries to Assumpink Creek, NJ. These areas were severely damaged by floods in 1938, 1955, 1967 and 1971. A description of the history of flooding along Assumpink Creek and its tributaries was presented with special emphasis also given thru maps, photographs, profiles and cross section for determination of the possible effects of future floods.			

Under authority of Section 206 of the 1960 Flood Control Act as amended the flood plain information was prepared by the U.S. Army Corps of Engineers Philadelphia District at the request of the Mercer County Planning Board and the New Jersey Department of Environmental Protection. The information should be considered for its historical nature. Since the publication of this FPI report other Flood Insurance studies have been undertaken and should also be consulted for more current information.

Accession For	
NTIS GRA&I	
DTIC TAB	
Unannounced	
Justification	
By	
Distribution/	
Availability Codes	
Avail and/or	
Special	
Dist	

For color
reproduct-
in black and

TO THE REQUESTOR:

This Flood Plain Information (FPI) Report was prepared by the Philadelphia District office of the U.S. Army Corps of Engineers, under the continuing authority of the 1960 Flood Control Act, as amended. The report contains valuable background information, discussion of flood characteristics and historical flood data for the study area. The report also presents through tables, profiles, maps and text, the results of engineering studies to determine the possible magnitude and extent of future floods, because knowledge of flood potential and flood hazards is important in land use planning and for management decisions concerning floodplain utilization. These projections of possible flood events and their frequency of occurrence were based on conditions in the study area at the time the report was prepared.

Since the publication of this FPI Report, other engineering studies or reports may have been published for the area. Among these are Flood Insurance Studies prepared by the Federal Insurance Administration of the Federal Emergency Management Agency, Flood Insurance Studies generally provide different types of flood hazard data (including information pertinent to setting flood insurance rates) and different types of floodplain mapping for regulatory purposes and in some cases provide updated technical data based on recent flood events or changes in the study area that may have occurred since the publication of this report.

It is strongly suggested that, where available, Flood Insurance Studies and other sources of flood hazard data be sought out for the additional, and, in some cases, updated flood plain information which they might provide. Should you have any questions concerning the preparation of, or data contained in this FPI Report, please contact:

U.S. Army Corps of Engineers
Philadelphia District
Custom House, 2nd and Chestnut Streets
Philadelphia, PA 19106

ATTN: Flood Plain Mgt. Services Branch, NAPEN-M

Telephone number: (215) 597-4807

NOTICE

THIS DOCUMENT HAS BEEN REPRODUCED
FROM THE BEST COPY FURNISHED BY
THE SPONSORING AGENCY. ALTHOUGH
IT IS RECOGNIZED THAT CERTAIN POR-
TIONS ARE ILLEGIBLE, IT IS BEING
RELEASED IN THE INTEREST OF MAKING
AVAILABLE AS MUCH INFORMATION AS
POSSIBLE.

APPROVED FOR PUBLIC RELEASE;
DISTRIBUTION UNLIMITED.

CONTENTS

	Page
PREFACE	i
BACKGROUND INFORMATION	1
Settlement	1
The Stream and Its Valley	1
Developments in the Flood Plain	3
FLOOD SITUATION	6
Sources of Data and Records	6
Flood Season and Flood Characteristics	6
Factors Affecting Flooding and Its Impact	7
Obstructions to floodflows	7
Flood damage reduction measures	7
Other factors and their impacts	8
Flood warning and forecasting	8
Flood fighting and emergency evacuation plans, ...	9
Material storage on the flood plain	9
PAST FLOODS	11
Summary of Historical Floods	11
Flood Records	11
Flood Descriptions	12
September 22, 1938	12
August 13-18, 1955	12
March 7, 1967	13
History of flooding in Trenton, New Jersey, area since 1692	13
August 28, 1971	14

CONTENTS (Continued)

	Page
FUTURE FLOODS	18
Floodway Design and Flood Hazard Area Design Floods	18
Standard Project Flood	19
Frequency	21
Hazards of Large Floods	21
Flooded areas and flood damages	21
Obstructions	22
Velocities of flow	22
Rates of rise and duration	25
Photographs, future flood heights	27
GLOSSARY	31

TABLES

Table	Page
1 Drainage Areas (Shabakunk, West Branch Shabakunk, and Little Shabakunk Creeks)	3
2 Population Trends and Projections of Mercer County by Municipalities	5
3 Flood Crest Elevations (Assunpink Creek at Trenton, New Jersey, U.S.G.S. Gage No. 4640)	11
4 Peak Flows for Floodway Design, Flood Hazard Area Design, and Standard Project Floods	19
5 Flood Elevations	20
6 Elevation Data (Bridges Across Shabakunk, West Branch Shabakunk, and Little Shabakunk Creeks)	23
7 Maximum Average Velocities (Shabakunk, West Branch Shabakunk, and Little Shabakunk Creeks)	26
8 Rates of Rise and Duration (Standard Project Flood)	27

CONTENTS (Continued)

PLATES

Plate		
1	General Map	Opposite Page i
2	Index Map	
3 - 27	Flooded Areas	
28	High Water Profile - Shabakunk Creek	
29	High Water Profile - West Branch Shabakunk Creek	
30	High Water Profile - Little Shabakunk Creek	
31	Selected Cross Sections - Shabakunk Creek	
32	Selected Cross Sections - West Branch Shabakunk Creek	
33	Selected Cross Sections - Little Shabakunk Creek	
34	Standard Project Flood Hydrographs	

At End of Report

FIGURES

Figure		Page
1	Fence obstructs floodflows on Little Shabakunk Creek	10
2 - 5	Aerial views of flooding during Hurricane Doria, August 28, 1971.	16 - 17
6	Future flood heights on Shabakunk Creek near Lawrenceville Road (U.S. Rte. 206)	28
7	Future flood heights on Shabakunk Creek at the Parkside Avenue bridge	29
8	Future flood heights on Little Shabakunk Creek at Princeton Pike (N.J. Rte. 583) bridge	29
9	Future flood heights on West Branch Shabakunk Creek near the Parkside Avenue	30




PLATE I

PREFACE

The portion of Mercer County covered by this report is subject to flooding by Shabakunk Creek, West Branch Shabakunk Creek, and Little Shabakunk Creek, all of which are tributaries to the Assunpink Creek. Commercial and residential properties along these streams have been severely damaged by floods in 1938, 1955, 1967, and 1971. The flood plain is extensively developed and may come under more pressure for development in the future. Although large floods have occurred in the past, studies indicate that even larger floods are possible.

This report presents flood hazard information which is important in land use planning and for management decisions concerning flood plain utilization. It includes a history of flooding along Assunpink Creek and its tributaries and identifies those areas that are subject to possible future floods. Special emphasis is given to these possible future floods through maps, photographs, profiles, and cross sections. The report does not provide solutions to flood problems; however, it does furnish a suitable basis for the adoption of land use controls to guide flood plain development and thereby prevent intensification of the loss problems. It will also aid in the identification of areas where other flood damage reduction techniques such as works to modify flooding and adjustments including flood proofing might be embodied in an overall flood plain management (FPM) program. Other FPM program studies -- those of environmental attributes and the current and future land use role of the flood plain as part of its surroundings -- would also profit from this information.

At the request of the Mercer County Planning Board and the New Jersey Department of Environmental Protection, this report was prepared by the Philadelphia District Office of the U.S. Army Corps of Engineers under the continuing authority provided in Section 206 of the 1960 Flood Control Act, as amended.

Assistance and cooperation of the Mercer County Planning Board, Free Public Library of Trenton, United States Geological Survey (U.S.G.S.), "Trenton Evening Times", and private citizens in supplying useful data and photographs for the preparation of this report is appreciated.

Additional copies of this report can be obtained from the Mercer County Planning Board. The Philadelphia District Office, upon request, will provide technical assistance to planning agencies in the interpretation and use of the data presented as well as planning guidance and further assistance, including the development of additional technical information.

BACKGROUND INFORMATION

Settlement

In the early years of the seventeenth century, the land which is now Mercer County was dominated by the Indians of the Lenni-Lenape Tribe. Settlers from New York ventured down over Indian trails which converged at the head of the tidewater at "Ye Falls of Ye De La Warre" and began trading with the Indians. The first settlement--now Trenton--was established at this site in 1676. Trenton, named for Judge William Trent of Philadelphia, had a most advantageous location along the Delaware River. Navigation on the river was limited by the falls and many cargoes had to pass through Trenton. From the time of its first settlement, Trenton was a major port on the Delaware River.

As Trenton developed and prospered, new communities formed rapidly in the surrounding areas. People settled along the numerous streams in Mercer County and, in particular, along the Assunpink, Shabakunk, West Branch Shabakunk, and Little Shabakunk Creeks. The fertile soil produced many agricultural products for shipment and use as raw materials in the early industries. Economically and militarily, the Trenton area played an important role in the Revolutionary War. After the war, as efforts were concentrated on industrial growth, many types of mills and industries were constructed along the waterways as the people took advantage of the ample supply of good quality water.

With the construction of the railroads and the Delaware Raritan Canal in the 1830's, even more raw materials were shipped to the Trenton area and it became one of the leading manufacturing cities of the nation. Much development occurred on the flood plains of Assunpink, Shabakunk, West Branch Shabakunk, and Little Shabakunk Creek as growth and subsequent expansion took place. At the present time, the flood plains of these creeks are highly developed in the Trenton area. Development of flood plain areas will continue at a rapid pace as the growth and expansion reduces the amount of other land available for building sites.

The Stream and Its Valley

Shabakunk Creek, West Branch Shabakunk Creek and Little Shabakunk Creek are tributaries to the Assunpink Creek, a major stream of the Delaware River Basin. The Assunpink Creek, with a drainage area of 89.4 square miles, originates in Monmouth County, New Jersey, but the largest portion of the watershed lies in Mercer County. The Assunpink Creek watershed is one of the ground water recharge areas for the large water-bearing formation underlying southern New Jersey.

All of the streams covered in this report lie within Mercer County and flow through low hills with the ground surface undulating slightly. The soil of the three watersheds is a light, loamy, alluvial type.

Shabakunk Creek, with a drainage area of 12.3 square miles, originates in Hope-well Township and flows southerly and then easterly to its confluence with the Assunpink Creek in Lawrence Township. Most of its watershed has been residentially developed and additional development of individual home sites and subdivisions is reducing the perviousness of the area. Overbank areas adjacent to the stream have heavy trees and brush with some short grass present. The stream has low banks with little vegetation or rock in the channel. The 6.2 mile study reach has a fairly uniform slope averaging 10 feet per mile.

West Branch Shabakunk Creek, with a drainage area of 4.9 square miles, originates in Ewing Township and flows southeasterly and then easterly to its confluence with Shabakunk Creek in Lawrence Township. The watershed has been highly developed and much of the area is impervious to rainfall. New commercial development is creating additional impervious areas. In general, the stream has high banks with little evidence of vegetation or rocks in the channel. Along several portions of the stream, a rectangular channel has been formed by retaining walls and buildings. The overbank area has scattered trees and brush with some grassy lawns. The 5.2 mile study reach, which has a steeper slope on the upper portion than on the lower portion, slopes an average of 20 feet per mile.

Little Shabakunk Creek, with a drainage area of 4.1 square miles, originates in Lawrence Township and flows southeasterly to its confluence with the Assunpink Creek. The watershed has been residentially developed and the amount of pervious area will decrease as new development occurs. The 3.4 mile study reach of Little Shabakunk Creek also has a fairly uniform slope averaging 15 feet per mile. Drainage areas of Shabakunk Creek, West Branch Shabakunk Creek and Little Shabakunk Creek are noted in Table 1 and shown on the General Map, Plate 1.

Typical of the temperate zones, the climate of Mercer County is moderate with temperatures that may drop below 20 degrees in the winter or rise above 85 degrees in the summer, January being the coldest month and July the warmest. The annual rainfall of 40 to 45 inches is rather evenly distributed over all the months. The prevailing winds are westerly and southwesterly during most of the year.

TABLE 1
DRAINAGE AREAS

Shabakunk, West Branch Shabakunk and Little Shabakunk Creeks

Location	Mileage Above Mouth	Drainage Area	
		<u>Tributary</u> sq. mi.	<u>Total</u> sq. mi.
<u>Shabakunk Creek</u>			
Confluence with Assunpink Creek	0	---	12.3
Downstream of Confluence with West Branch Shabakunk Creek	2.19	4.9	10.8
Upstream of Confluence with West Branch Shabakunk Creek	2.19	---	5.9
Bull Run Rd.	6.14	---	2.8
<u>West Branch Shabakunk Creek</u>			
Confluence with Shabakunk Creek	0	---	4.9
<u>Little Shabakunk Creek</u>			
Confluence with Assunpink Creek	0	---	4.1

Developments in the Flood Plain

Shabakunk Creek has commercial development on the flood plain in the vicinity of Brunswick Pike (U.S. Rte 1). A large shopping center at this location was inundated by the flood of August 1971. From this point upstream to its headwaters, most of the flood plain development has been residential subdivisions, with the individual lots adjoining the stream.

West Branch Shabakunk Creek has the most concentrated development of the three streams in this study. Near Olden Avenue, a furniture store and restaurant abut the channel. Between Spruce Street and Olden Avenue, numerous commercial buildings have been constructed on the flood plain. At Parkside Avenue, commercial buildings are also constructed on the flood plain and the stream passes beneath a new row of stores. From the second crossing of Olden Avenue upstream to Carlton Avenue, the flood plain has highly concentrated residential development. Many of these properties have been damaged by floods in the past. The upper portion of the West Branch Shabakunk Creek watershed is presently undergoing residential development.

Little Shabakunk Creek also has commercial development near Brunswick Pike (U.S. Rte. 1). Upstream of this point most of the flood plain development has been residential. The upper portion of Little Shabakunk Creek flows through the campus of Rider College and several buildings are located on the flood plain in this area.

Table 2 entitled "Population Trends and Projections of Mercer County by Municipalities" shows a slight decrease in the urban population of Trenton, but an overall population increase in Mercer County. As the population increases and shifts outward from urban areas, flood plain land in suburban and rural areas will come under increasing pressure for development.

TABLE 2
POPULATION TRENDS AND PROJECTIONS OF MERCER COUNTY BY MUNICIPALITIES

Area	Population Trends			Population Projections		
	1960(a)		1970(a)	1980		1990
	Number	Percent Change	Number	Number	Percent Change	Number
East Windsor Township	2,298	79.0	11,736	36,000	206.7	59,330
Ewing Township	26,628	58.1	32,831	36,700	11.8	39,000
Hamilton Township	65,035	58.0	79,609	100,000	25.6	140,000
Hightstown Borough	4,317	16.3	5,431	5,800	6.8	6,330
Hopewell Borough	1,928	3.2	2,271	2,600	14.5	2,670
Hopewell Township	7,818	65.3	10,030	13,200	31.6	22,670
Lawrence Township	13,665	60.8	19,567	27,600	41.1	40,000
Pennington Borough	2,063	22.7	2,151	2,500	26.0	2,670
Princeton Borough	11,890	-2.8	12,311	12,800	3.9	13,300
Princeton Township	10,411	92.5	13,651	17,850	30.8	23,000
Trenton	114,167	-40.8	104,638	94,800	-9.4	91,330
Washington Township	2,156	17.0	3,311	6,600	99.4	13,470
West Windsor Township	4,016	59.4	6,431	13,300	107.0	28,670
Mercer County	266,392	15.9	303,968	369,750	21.6	482,440
						30.5

(a) Figures taken from U.S. Bureau of Census

FLOOD SITUATION

Sources of Data and Records

There are no stream gaging stations on Shabakunk Creek, West Branch Shabakunk Creek, and Little Shabakunk Creek. However, the United States Geological Survey maintains a gaging station on the Assunpink Creek in the City of Trenton. The location of the gaging station is shown on the General Map. Records from this gage were used in the hydrologic computations for each of the three streams in this study.

High water elevations from Hurricane Doria (August 27-28, 1971) on the Shabakunk Creek and West Branch Shabakunk Creek were obtained from Special Report 37 entitled "Floods of August and September 1971 in New Jersey" as prepared by the United States Department of the Interior, Geological Survey, 1972. Geological data used in the preparation of this study was obtained from Special Report 19 entitled "Ground Water Resources of Mercer County, New Jersey" as prepared by the United States Department of the Interior, Geological Survey, 1962. To supplement the records at the gage and the other available data, newspaper files, historical documents, and records were searched for information concerning past flooding. From these records, a knowledge of flooding on Shabakunk Creek, West Branch Shabakunk Creek, and Little Shabakunk Creek has been developed.

Maps prepared for this report were based on photogrammetric mapping supplied by the Mercer County Planning Board. Structural dimensions of bridges and culverts were obtained from field surveys by personnel from the Philadelphia District, Corps of Engineers.

Flood Season and Flood Characteristics

Three of the four highest floods on Shabakunk Creek, West Branch Shabakunk Creek, and Little Shabakunk Creek were the result of heavy rainfall associated with hurricanes. These floods occurred in September 1938, August 1955 (Hurricane Diane), and in August 1971 (Hurricane Doria). However, heavy rainfall on the basin can cause major floods during all seasons of the year. During floods, flows can increase from normal to peak quantities in a relatively short period of time with high velocities in the main channel.

Flood stages on the Assunpink Creek produce a backwater effect that increases flood heights at the mouth of Shabakunk Creek and Little Shabakunk Creek. In addition to greater depths of floodwaters, larger areas of the flood plain are inundated resulting in increased damage to surrounding development.

Factors Affecting Flooding and Its Impact

Obstructions to floodflows - Natural obstructions to floodflows include trees, brush and other vegetation growing along the stream banks in floodway areas. Man-made encroachments on or over the streams such as dams, bridges, and culverts can also create more extensive flooding than would otherwise occur. Figure 1 shows a possible obstruction to floodflow.

During floods, trees, brush and other vegetation growing in floodways impede floodflows, thus creating backwater and increased flood heights. Trees and other debris may be washed away and carried downstream to collect on bridges and other obstructions to flow. As floodflows increase, masses of debris break loose and a wall of water and debris surges downstream until another obstruction is encountered. Debris may collect against a bridge until the hydraulic load exceeds its structural capacity and the bridge is destroyed. The limited capacity of obstructive bridges or culverts, debris plugs at the culvert mouth or a combination of these factors retard floodflows and result in flooding upstream, erosion around the culvert entrance and bridge approach embankments and possible damage to the overlying roadbed.

In general, obstructions restrict floodflows and result in overbank flows and unpredictable areas of flooding, destruction of or damage to bridges and culverts, and, an increased velocity of flow immediately downstream. It is impossible to predict the degree or location of the accumulation of debris; therefore, for the purposes of this report, it was necessary to assume that there would be no accumulation of debris to clog any of the bridge or culvert openings in the development of flood profiles.

The 5 small dams located on Shabakunk Creek and Little Shabakunk Creek have no flood control capacities nor do they seriously alter flow characteristics of floodwaters.

Shabakunk Creek, West Branch Shabakunk Creek, and Little Shabakunk Creek are spanned by 51 bridges. Pertinent information on all bridges can be found in Table 6 on Page 23. Many of these bridges are obstructive to floodflows.

Flood damage reduction measures - There are no existing, proposed, or authorized flood control or related measures in the study area or upstream in the watershed. However, the State of New Jersey enacted an encroachment law in 1929 which is essentially a preventive flood loss measure. The law is known as the "1929 Encroachment Law (RS 58:1-26)" and is administered by the Division of Water Resources of the Department of Environmental Protection. The law reads in part as follows:

"No structure within the natural and ordinary high water mark of any stream shall be made by any public authority or private person or corporation without notice to the (Division) and in no case without complying with such conditions as the (Division) may prescribe for preserving the channel and providing for the flow of water therein to safeguard the public against danger from the waters impounded or affected by such a structure and this prohibition shall apply to any renewal of existing structures."

Under the provision of this law, the Division issues permits for the construction of bridges, culverts, fills, walls, channel improvements, pipe crossings and other encroachments located within the natural and ordinary high water mark of the stream. Another New Jersey encroachment law (Chapter 229, Laws of 1938, amending a previous law known as RS 40:56-1), permits municipalities of the State to construct improvements, remove obstructions, define the location, establish widths, grades, and elevations of any stream and to prevent encroachments thereon--subject to approval by the State of the flood carrying capacity to be provided. Under this law, counties in New Jersey are permitted to assist municipalities in local flood damage alleviation programs.

The New Jersey Flood Plain Designation and Marking Law, enacted in 1962 [NJSA 58:16A(50 et. seq.)] and as amended December 14, 1972, empowers the Division of Water Resources to delineate and mark flood hazard areas, to authorize the Department of Environmental Protection to adopt land use regulations, and to coordinate effectively the development, dissemination and use of information on floods and flood damage that may be available. The development of adequate flood plain information, as furnished in this report, will enable state and local authorities to further implement existing statutes and regulations.

Other factors and their impacts - The impact of flooding along Shabakunk Creek, West Branch Shabakunk Creek, and Little Shabakunk Creek can be affected by the ability of local residents to anticipate and effectively react to a flood emergency. Efficient flood warning and forecasting systems can give homeowners, business, and industry valuable time to remove damageable materials from low-lying areas. Increased damages to downstream areas can also be reduced if floatable materials stored on the flood plain can be removed before being carried downstream to block bridge and culvert openings. Implementation of effective flood fighting and emergency evacuation plans can further reduce flood damages and the incidence of personal injury and death once the creek has reached flood stage.

Flood warning and forecasting - Inhabitants of the area depend entirely on the usual warnings issued through radio, television, and the local press media. The National Oceanic and Atmospheric Administration (NOAA) maintains year-round surveillance of weather conditions at Trenton, New Jersey. Commercial radio stations receive information on hurricanes, tornadoes, and flash flood warnings and broadcast to the public through the

Emergency Weather Network in cooperation with the New Jersey Civil Defense Disaster Control (CD-DC). The State CD-DC also receives the information directly from Trenton and disseminates the forecasts through its own communications system to area, county and local Civil Defense Offices.

Flood fighting and emergency evacuation plans - Although there are no formal flood fighting or emergency evacuation plans for Shabakunk Creek, West Branch Shabakunk Creek and Little Shabakunk Creek during a flood emergency, area residents are alerted through local communications media by the Mercer County Civil Defense Office. The office maintains communications with the State Civil Defense Headquarters and coordinates flood fighting evacuation and rescue activities on a county-wide basis with local agencies.

Material storage on the flood plain - The flood plain of Shabakunk Creek, West Branch Shabakunk Creek, and Little Shabakunk Creek is occupied mainly by residential structures and commercial establishments. Very little buoyant material is stored on the flood plain, but waste containers, small sheds, and wooden foot bridges that are unrestrained may be carried away by floodflows. Also, vehicles parked at shopping centers may be inundated by rapidly rising floodwaters and carried downstream with other debris. During floods, all types of buoyant material and objects can clog downstream bridge openings and create more hazardous flooding problems and serious damage to structures.




Figure 1 - Fence across Little Shabakunk Creek could be obstructive during times of floodflow.

PAST FLOODS

Summary of Historical Floods

Floods causing significant damage to the area occurred in September 1938, August 1955, March 1967, and August 1971. High water marks recorded during the flood of August 1971 indicate this flood to be the flood of record for Shabakunk Creek and West Branch Shabakunk Creek.

Flood Records

Gage records are not available for Shabakunk Creek, West Branch Shabakunk Creek and Little Shabakunk Creek. However, floodflows recorded on the Assunpink Creek at Trenton, New Jersey, reflect floods that occurred at the same time on these three streams.

Flood data on the Assunpink Creek was obtained by the United States Geological Survey at Trenton, New Jersey. The Gage (No. 4640) has been in operation from January 1924 to the present. Flood crest elevations and discharges for known floods at this gaging station are shown in Table 3. High water elevations on Shabakunk Creek and West Branch Shabakunk Creek, as taken from Special Report 37, are shown in Table 5 on page 20.

TABLE 3
FLOOD CREST ELEVATIONS
Assunpink Creek at Trenton, New Jersey, U.S. Geological Survey
Gage No. 4640

Date of Crest	Estimated Peak Discharge	Stage ^(a)	Elevation ^(b)
	cfs	Feet	Feet-m.s.l.d.
August 28, 1971	3,920	13.46	38.22
September 22, 1938	3,320	10.74	35.50
March 7, 1967	2,660	9.91	34.67
August 13, 1955	2,400	9.29	34.05
July 23, 1938	2,370	8.90	33.66
February 28, 1958	2,300	9.16	33.92

(a) Bankfull stage is 8 feet.

(b) Datum of Gage is 24.76 feet above mean sea level datum (New Jersey Geological Survey bench mark).

Flood Descriptions

The following descriptions provide graphic accounts of the large floods that occurred on Shabakunk Creek, West Branch Shabakunk Creek, and Little Shabakunk Creek in the vicinity of Trenton, New Jersey, and neighboring communities.

September 22, 1938 - A violent fall hurricane with heavy rain and wind struck New Jersey as well as the other North Atlantic States and Canada.

EXCERPTS FROM THE TRENTON EVENING TIMES,^(a)
SEPTEMBER 22, 1938

Thousands Left Homeless; Gigantic Rescue Job Starts; River Stirs Fears of Flood

The ever-lengthening roster of the dead from an equinoctial hurricane which struck the North Atlantic States with a savageness unequalled in a hundred years neared the 250 mark today--and still the tragic figures mounted.

The damage to property--to hundreds of

smashed boats, to growing or maturing crops, to homes, utilities, public buildings, transportation and communications--was beyond calculation, rising to uncounted millions of dollars. How many thousands were homeless could not even be guessed.

Delaware at Trenton Is Rising at Alarming Pace

Danger of flood faced Trenton today as the Delaware River, swollen by excessive rainfall, raged along at a level that hourly looked more menacing.

The swollen subsidiaries of the river gave further concern to harrassed residents. In one section of Hamilton Township, a number of persons were marooned and were rescued by police in boats.

The Assunpink Creek, swollen beyond capacity, rose over its banks and flooded cellars of property nearby. Outlying districts of Trenton were particularly hard hit by the storm and its ensuing flood, especially in Hamilton Township where roads were blocked and trees blown down. In Ewing Township nearly two feet of water covered the Shabakunk and Upper Ferry Roads, stalling cars and creating a traffic hazard.

August 13 - 18, 1955 - On August 13, 1955, heavy rainfall accompanying Hurricane Connie caused flooding and damage on the Assunpink Creek and its tributaries, Shabakunk Creek, West Branch Shabakunk Creek, and Little Shabakunk Creek. Backwater from the Assunpink Creek caused additional flooding at its confluence with Shabakunk Creek and Little Shabakunk Creek. On August 18, 1955, Hurricane Diane followed Hurricane Connie and caused the great disaster on the Delaware River. Backwater from the river caused severe damage along the Assunpink Creek in the City of Trenton. Due to the magnitude of this flood on the Delaware River, flooding on the Shabakunk Creek and Little Shabakunk Creek received only minor attention in reportings by local news media.

^(a)Simulated from newspaper clippings.

March 7, 1967 - A gale-powered northeaster dumped heavy snows over a large portion of the United States and over 3 inches of rain on the Trenton area.

EXCERPTS FROM THE TRENTON TIMES,^(a)

MARCH 7, 1967

Deluge Perils Entire State

The Delaware Valley was hit today with the worst flood in 10 years and plants and homes were affected by the high water. The total rainfall in the storm that began Saturday measured 3.32 inches by 11:30 a.m. today. In the past 24 hours there was 2.46 inches of rain...Thomas

Sweeney, planning manager of the Goodall Rubber Company, said the plant was forced to shut down its boilers about 9:30 a.m. because the boiler room was flooding...There are 30 bridges in Mercer County crossing the Assunpink and the creek was expected to overflow all of them.

Following are newspaper excerpts giving light to the history of flooding in the Trenton, New Jersey, area since 1692:

EXCERPTS FROM THE SUNDAY TIMES ADVERTISER, TRENTON, NEW JERSEY,^(a)
AUGUST 29, 1971

Floods, An Old 1692-1903 Story for Delaware Valley

It started raining here early in the afternoon of October 8, 1903, and continued for about nine hours. The next day the skies really opened up, dumping 5-1/2 inches on the area. One day later the Delaware River and surrounding streams went on a rampage. Another flood occurred five months later. This time it was the breakup of ice jams rather than heavy rain that caused the flooding.

The most destructive flood ever to swamp the Delaware Valley was the drought and rain-induced tragedy of August 1955. Early that summer there wasn't a drop of rain for weeks. Then, on August 7, came the rain--2.9 inches of it in about an hour.

Five days later, with the ground still soaked, Hurricane Connie came roaring up the Atlantic Coast. It dropped more than five inches of rain on this area in what seemed a never-ending 32 hours.

Six days later on August 18, Hurricane Diane came along with five more inches of rain. The three days of flooding that ensued will be remembered even by today's 18-year olds.

The earliest flood recorded here was that of 1687. It was reported as "the great flood and rupture" at the falls of the Delaware and it was "followed by great sickness".

1692 - This one, "the first great flood" here was attributed to the melting snow at near end of winter.

1731 - This one happened late in February and was referred to as "the greatest freshet in the Delaware since 1692".

1733 - Of this one the "New England Weekly Journal" reported: "The freshets have done much damage at Trenton and carried away the dam of the iron works and the dam of the grist mill".

1822 - The Warren Street bridge was swept away in this freshet on February 21. A day later, the Greene (now Broad) Street bridge gave away.

(Between 1692 and 1903 there were 43 freshets in the Delaware, the two worst occurring in 1841 and 1862).

1936 - March 19, 1936. Yardley and Morrisville were hit hard by this one and so was the "Island" section of Trenton where some 200 families were marooned.

Among the flood episodes to follow were those of 1950, 1951, 1967, and 1968.

Let us hope that the late summer of 1971 does not become part of a tragic record that started in 1687.

^(a)Simulated from newspaper clippings.

August 28, 1971 - Hurricane Doria caused the severest flooding in the history of New Jersey, with loss of life and untold damage and destruction throughout the state. The following excerpts from various newspapers appeared during a three-day period:

EXCERPTS FROM THE SUNDAY TIMES ADVERTISER, TRENTON, NEW JERSEY, (a)
AUGUST 29, 1971

Record Rain, Floods Rout Thousands; Cahill Weighs A State of Emergency

Record flooding of rivers and streams following the most intense rainfall in New Jersey history drove thousands of families from their homes and almost paralyzed many sections of the state yesterday.

Governor William T. Cahill's office said the Governor probably will declare a state of emergency... About one-fourth of Hamilton

Township was declared to be in a state of emergency by Mayor Raymond I. Dwier. The most serious damage in Mercer County was caused by the Assunpink Creek, which crested at 13.45 feet, almost seven feet above flood stage. The main line of the Penn Central was shut down when about three feet of water from clogged Assunpink flowed across the tracks at the Clinton Street Station.

EXCERPTS FROM THE TRENTONIAN, TRENTON, NEW JERSEY, (a)
AUGUST 30, 1971

Doria Leaves 3 Dead, \$15 Million Ruin Here U.S. Aid Sought by City, Hamilton

Hamilton Township and Trenton mounted massive rescue operations this weekend, in the wake of Hurricane-fed floods that caused up to three deaths, drove hundreds of families from their homes and ruined an estimated \$15 million worth of property... Three hundred persons were evacuated from homes in Hamilton, and another three hundred in Trenton... It was the Assunpink Creek running through West

Hamilton and North and South Trenton that caused major damage, rising to nearly 14 feet... The flooding halted all Penn Central rail traffic through Trenton for 28 hours, leaving the tracks 40 inches under water in places... In Ewing Township Police Capt. Robert Plaag said the storm and floods probably cost around \$450,000, including the physical damages and costs of emergency operations.

(a) Simulated from newspaper clippings.

EXCERPTS FROM THE EVENING TIMES, TRENTON, NEW JERSEY(a)
AUGUST 31, 1971

Industry Hard Hit by Flood

The Ewing-Lawrence Sewer Authority (ELSA) treatment plant is operating at three quarters capacity today in the wake of flooding which caused more than \$225,000 damage to the sewer system.

William Higgins, director of the authority, reported that flood-waters which swamped the headquarters on Whitehead Road, Lawrence Township, caused some \$75,000 damage to the treatment plant. Also, an estimated \$150,000 will be needed to remove silt from collector lines.

Industrial plants along the Assunpink continued their mop-up operations today. James Floyd of Stokes Molded Products said today that damage totaled \$1 million, and added he has no idea when the plant can begin operations again.

At the nearby Crescent Wire plant damage was estimated at \$50,000. The plant probably will be closed for two weeks, putting some 300 people out of work.

EXCERPTS FROM THE TRENTONIAN, TRENTON, NEW JERSEY (a)
AUGUST 31, 1971

Doria Damage Set at \$25 Million

The Doria floods caused an estimated \$25 million in property damages, according to the "flash" report given Gov. William T. Cahill by William Falcey, Mercer County civil defense coordinator.

The civil defense chief said preliminary reports indicated \$9 million damages in Hamilton Township and \$4.5 million damages in Trenton

with the balance in the suburbs.

The worst day for Public Service [meaning electric and gas], according to the spokesman, was Saturday, when more than 15,000 area residents were without electricity. Hardest hit was Ewing Township, where the rampaging waters of the Shabakunk Creek overran a substation and knocked out power for 6,000 customers.

The following aerial photographs, Figures 2 through 5, show the vast area that was flooded during Hurricane Doria, August 28, 1971.

(a) Simulated from newspaper clippings.



Figure 2 - Shabakunk Creek between Brunswick Pike (U.S. Rte. 1) and Princeton Pike N.J. Rte. 583 overflows into the Lawrence Shopping Center.




Figure 3 - Little Shabakunk Creek flows under Brunswick Pike (U.S. Rte. 1) on the left side of the photograph, but inundates a large portion of roadway and the adjacent area.




Figure 4 - West Branch Shabakunk Creek flows under Olden Avenue between the Reading R.R. on the left side and Arctic Parkway on the upper right side. Commercial establishments on both sides of the stream suffered heavy damages.




Figure 5 - West Branch Shabakunk Creek flows under Prospect Street in the upper right-hand side of the photograph, but inundates the Ewing Drive Theatre and numerous commercial buildings. Inundation of the electrical substation in the center of the photograph caused a power failure that affected thousands of residents.

FUTURE FLOODS

Floods of the same or larger magnitude as those that have occurred in the past could occur in the future. Large floods have been experienced in the past on streams with similar geographical and physiographical characteristics as those found in the study area. Similar combinations of rainfall and runoff which caused the floods could occur in the study area. Therefore, to determine the flood potential of the study area, it was necessary to consider storms and floods that have occurred in regions of like topography, watershed cover, and physical characteristics. Discussion of the future floods in this report has been limited to those that have been designated as the Floodway Design Flood (FDF), the Flood Hazard Area Design Flood (FHADF), and the Standard Project Flood (SPF). In the hydrologic region that includes the Shabakunk Creek Watershed, the Floodway Design Flood is equivalent to a flood having an average recurrence interval of once in 100 years. The 100-year event is designated the Intermediate Regional Flood (IRF) by the Corps of Engineers. A reasonable upper limit of expected flooding in the area is represented by the Standard Project Flood. The Floodway Design Flood and the Flood Hazard Area Design Flood may reasonably be expected to occur more frequently although they will not be as severe as the infrequent Standard Project Flood.

Floodway Design and Flood Hazard Area Design Floods

The State of New Jersey defines "Floodway" as the channel and portion of the adjacent flood plain necessary to preserve the natural regimen of a stream for the reasonable passage of the Floodway Design Flood. The "Flood Hazard Area" includes the floodway and any additional portions of the flood plain inundated by the Flood Hazard Area Design Flood.

Both the Floodway Design Flood and the Flood Hazard Area Design Flood are used extensively by the State of New Jersey for flood plain management programs. Methods for the determination of these design floods are contained in "New Jersey Flood Hazard Report No. 1, Delineation of Flood Hazard Areas". The method applied "multiples" to the mean annual flood as determined by regional analysis prescribed in New Jersey Water Resources Circular No. 13, "Floods in New Jersey: Magnitude and Frequency". This circular was prepared in 1964 by the U.S. Geological Survey in cooperation with the State of New Jersey. Peak flows for both the Floodway Design Flood and the Flood Hazard Area Design Flood at selected locations are given in Table 4. The relative water surface elevations for the Floodway Design Flood and the Flood Hazard Area Design Flood are shown on Plates 28 through 30.

Standard Project Flood

The Standard Project Flood is defined as a major flood that can be expected to occur from a severe combination of meteorological and hydrological conditions that are considered reasonably characteristic of the geographical area in which the study is located, excluding extremely rare combinations. The Corps of Engineers, in cooperation with NOAA, has made comprehensive studies and investigations based on the past records of experienced storms and floods and has developed generalized procedures for estimating the flood potential of streams. Peak discharges for the Standard Project Flood at selected locations in the study area are given in Table 4. Discharge hydrographs for the Standard Project Flood at selected locations are shown on Plate 34. Relative water surface elevations for the Standard Project Flood are shown on Plates 28 through 30.

Table 5 gives flood elevations for the Standard Project Flood, Flood Hazard Area Design Flood, Floodway Design Flood, and the flood of August 28, 1971, Hurricane Doria.

TABLE 4
PEAK FLOWS FOR FLOODWAY DESIGN, FLOOD HAZARD AREA DESIGN,
AND STANDARD PROJECT FLOODS

Location	River Mile	Drainage Area Sq. Mi.	Floodway Design Flood Discharge cfs	Flood Hazard Area Design Flood Discharge cfs	Standard Project Flood Discharge cfs
<u>Shabakunk Creek</u>					
Confluence with Assunpink Creek	0.0	12.3	2,500	3,150	6,300
Downstream of confluence with West Branch Shabakunk Creek	2.19	10.8	2,250	2,800	5,500
Upstream of confluence with West Branch Shabakunk Creek	2.19	5.9	1,400	1,800	3,300
Bull Run Rd. (Study Limit)	6.14	2.8	750	950	1,800
<u>West Branch Shabakunk Creek</u>					
Confluence with Shabakunk Creek	0.0	4.9	1,200	1,500	2,400
<u>Little Shabakunk Creek</u>					
Confluence with Assunpink Creek	0.0	4.1	1,100	1,400	2,050

TABLE 5
FLOOD ELEVATIONS

Stream and Location	Mileage Above Mouth	Elevation ^(a)			Aug. 28, 1971 (Hurricane Doria)
		Standard Project Flood (SPF)	Flood Hazard Area Design Flood (FHADF)	Floodway Design Flood (FDF)	
<u>Shabakunk Creek</u>					
Lawrence Twp., N.J., 40 ft. downstream from mouth of West Branch Shabakunk Creek, left bank	2.18	65.4	62.7	62.2	63.7
Braeburn Heights, N.J., 1 mile northeast, near end of Whitehead Rd. extension	2.76	67.6	65.5	64.8	66.2
Braeburn Heights, N.J., just upstream from Ewingville Rd. (Parkside Ave.), right bank	3.57	78.0	76.4	75.7	76.4
Braeburn Heights, N.J., near Hollow Brook Rd. and Claflin Ave. dumping area, left bank	4.17	80.9	79.9	79.4	80.6
Ewingville, N.J., 50 ft. upstream from Green Lane bridge, right bank	4.48	86.0	84.0	83.4	84.1
Ewingville, N.J., upstream from Sylvia Lake Dam, right bank	4.90	95.4	94.0	93.5	94.2
Ewingville, N.J., near Ewingville and Federal City Roads, right bank	5.27	97.7	95.0	94.2	97.3
Ewingville, N.J., near end of Lopatcong Drive, right bank	5.92	112.1	109.9	109.2	110.2
<u>West Branch Shabakunk Creek</u>					
Trenton, N.J., on Fourth Street, 80 ft. upstream of Spruce Street, left bank	0.42	66.6	64.8	64.3	67.9
Trenton, N.J., 100 ft. upstream from Olden Avenue bridge, left bank	0.81	72.9	71.4	69.6	71.6
Trenton, N.J., 80 ft. upstream from Reading R.R. bridge, left bank	0.95	73.7	72.4	71.6	72.6
Trenton, N.J., 80 ft. upstream from Prospect Street bridge, left bank	1.19	76.4	74.5	73.9	75.4
^(a) Feet, mean sea level datum.					

Frequency

Regionalized frequency curves of peak flows were developed at selected stations along Shabakunk Creek, West Branch Shabakunk Creek, and Little Shabakunk Creek by methods prescribed in New Jersey Water Resources Circular No. 13, "Floods in New Jersey: Magnitude and Frequency".

The curves represent the frequency of floodflows up to a magnitude of once in 100 years (Floodway Design Flood). The curves, which are available upon request, reflect the judgment of engineers who have studied the area and are familiar with the region; however, it must be regarded as approximate and should be used with caution in connection with any planning of flood plain use.

The Standard Project Flood is considered the reasonable upper limit of expected flooding, but floods of even greater magnitude have a probability of occurring in the study area. Frequencies of floods equivalent to the Standard Project Flood or larger can be obtained through extrapolation of the curve, but it is not practical to assign a frequency to such large flows as their occurrence is so extremely rare.

Hazards of Large Floods

The extent of damage caused by any flood depends on the topography of the area flooded, depth and duration of flooding, velocity of flow, rate of rise, and developments in the flood plain. A Floodway Design Flood, Flood Hazard Area Design Flood, or Standard Project Flood on Shabakunk Creek, West Branch Shabakunk Creek, and Little Shabakunk Creek would result in the inundation of residential and commercial properties in the study area. Deep floodwater flowing at high velocity and carrying floating debris would create conditions hazardous to persons and vehicles attempting to cross flooded areas. In general, floodwater three or more feet deep and flowing at a velocity of three or more feet per second could easily sweep an adult person off his feet, thus creating definite danger of injury or drowning. Rapidly rising and swiftly flowing floodwater may trap persons in homes that are ultimately destroyed, or in vehicles that are ultimately submerged or floated. Waterlines can be ruptured by deposits of debris and the force of floodwaters, thus creating the possibility of contaminated domestic water supplies. Damaged sanitary sewer lines and sewage treatment plants could result in the pollution of floodwaters creating health hazards. Isolation of areas by floodwater could increase dangers during medical, fire, or law enforcement emergencies.

Flooded areas and flood damages - The areas along Shabakunk Creek, West Branch Shabakunk Creek, and Little Shabakunk Creek that would be flooded by the Standard Project Flood are shown on Plate 2 which is also an index map to Plates 3 through 27. Areas that would be flooded by the Floodway Design Flood, Flood Hazard Area Design Flood, and the Standard Project Flood are shown in detail on Plates 3 through 27. The actual limits of overflow may vary slightly from those shown on the maps because of the accuracy limitation of the aerial mapping.

On Shabakunk Creek, floodwaters may inundate a large portion of the Lawrenceville Shopping Center on Brunswick Pike (U.S. Route 1). Numerous bridges, roads, and tracks of the Reading Railroad are also subject to flooding. Residential areas along Little Shabakunk Creek and stores in the vicinity of Brunswick Pike (U.S. Route 1) may be flooded. On West Branch Shabakunk Creek, commercial buildings near Olden and Prospect Avenues are subject to flooding, and an electric substation may be flooded and put out of service as it was during Hurricane Doria in August 1971. In addition to residential and commercial structures, utilities and sanitary sewer lines may be damaged or destroyed by floodwaters.

Considerable damages to the facilities would occur during the Floodway Design and the Flood Hazard Area Design Floods. However, due to the wider extent, greater depths of flooding, higher velocity of flow and longer duration of flooding during a Standard Project Flood, damage would be more severe than during the Floodway Design and the Flood Hazard Area Design Floods. Plates 28 through 30 show water surface profiles for all three design floods. Depth of flow in the channel can be estimated from these illustrations. Typical cross sections at selected locations, together with the water surface elevation and lateral extent of the design floods, are shown on Plates 31 through 33.

Obstructions - During flooding conditions, debris can collect on bridges and culverts, thereby decreasing their carrying capacity and causing greater water depths (backwater effect) upstream of the structures. Since the occurrence and amount of debris are indeterminate factors, only the physical characteristics of the structures were considered in preparing profiles of the Floodway Design, Flood Hazard Area Design, and Standard Project Floods. Similarly, the maps of flooded areas show the backwater effect of obstructive bridges and culverts, but do not reflect increased water surface elevation that could be caused by debris collecting against the structures, or by deposition of silt in the stream channel under structures. As previously indicated, there are 5 dams within the study area that have no flood control capacities and will not seriously alter the flow characteristics of floodwaters. Of the 51 bridges crossing Shabakunk Creek, West Branch Shabakunk Creek, and Little Shabakunk Creek, 41 are obstructive to the Floodway Design Flood, 46 are obstructive to the Flood Hazard Area Design Flood and 48 are obstructive to the Standard Project Flood. Table 6 shows water surface elevations for all three design floods at the bridges.

Velocities of flow - During floods, water is forced to pass over lands not normally inundated, causing a wide range of velocities to occur. The water flowing in the deeper portions of the stream channel will be faster than in the more shallow overbank areas. Velocities of flow will also vary from one location upstream to the next area downstream as stream characteristics change. Some important factors are changes in bed slope, size and shape of channel and overbank areas, vegetation cover, materials composing the stream bed, and increased volumes of water to be carried by the stream possibly coming from tributaries, or

direct storm runoff. Soil may be eroded by velocities greater than 2 feet per second while debris and silt will be deposited at slower velocities. For the same location, it is possible to have severe erosion of the stream banks occur simultaneously with deposition of alluvial soils on the flood plain.

TABLE 6
ELEVATION DATA
Bridges Across Shabakunk, West Branch Shabakunk, and Little Shabakunk Creeks

Bridges Across Shabakunk, West Branch Shabakunk, and Little Shabakunk Creeks					
Identification	Mileage Above Mouth	Under- clearance Elev. (a) Feet-m.s.l.d.	Water Surface Elevation		
			Floodway Design Flood (b) Feet-m.s.l.d.	Flood Hazard Area Design Flood (b) Feet-m.s.l.d.	Standard Project Flood (b) Feet-m.s.l.d.
<u>Shabakunk Creek</u>					
Box culvert: Delaware and Raritan Canal, Penn Central R.R., New Jersey Rte. 147	0.26	46.1	50.6	51.6	55.8
Brunswick Pike (U.S. Rte. 1)	0.91	54.2	53.7	54.2	58.7
Footbridge	1.40	54.1	57.0	58.0	61.6
Princeton Pike (N.J. Rte. 583)	1.46	57.1	57.3	59.2	63.0
Lawrenceville Rd. (U.S. Rte. 206)	1.72	57.4	61.2	62.0	65.4
Reading R.R.	3.12	71.2	73.4	73.6	74.8
Parkside Ave.	3.57	72.0	75.7	76.4	78.0
Green Lane	4.47	80.7	83.3	83.9	85.9
Ewingville Rd.	5.27	93.9	94.2	95.0	97.7
Private Farm Rd.	5.63	100.4	101.7	102.3	104.4
Bull Run Rd.	6.14	111.9	112.1	113.0	114.4 ^(d)
<u>West Branch Shabakunk Creek</u>					
Spruce St.	0.40	64.6	64.2	64.7	66.5
Footbridge	0.48	64.8	65.5	66.1	68.8
Footbridge	0.57	64.9	67.3	68.3	69.3
Private Driveway	0.67	67.4	68.9	69.4	70.4
Olden Ave.	0.79	67.7	69.6	71.4	72.9
Reading R.R.	0.93	70.5	71.6	72.4	73.7
Prospect St.	1.17	72.8	73.6	74.5	76.4
Parkside Ave.	1.62	76.4	80.0	80.1	82.1
Box culvert (Shopping Center)	1.63	80.9	80.1	80.3	82.3
Private Driveway	1.75	80.0	80.7	81.4	82.8

TABLE 6 (Continued)

ELEVATION DATA
Bridges Across Shabakunk, West Branch Shabakunk, and Little Shabakunk Creeks

Identification	Mileage Above Mouth	Under- clearance Elev. (a) Feet-m.s.l.d.	Water Surface Elevation		
			Floodway Design Flood(b)	Flood Hazard Area Design Flood(b)	Standard Project Flood(b)
			Feet-m.s.l.d.	Feet-m.s.l.d.	Feet-m.s.l.d.
			Feet-m.s.l.d.	Feet-m.s.l.d.	Feet-m.s.l.d.
<u>West Branch Shabakunk Creek</u> (Continued)					
Pennington Ave. (N.J. Rte. 31)	1.82	83.3	82.7	84.5	86.1
Olden Ave.	2.15	83.4	85.0	85.4	87.1
Thurston Ave.	2.32	85.0	85.3	86.7	87.2
Central Ave.	2.56	89.3	88.3	89.9	90.4
Footbridge	2.68	89.2	88.7	90.6	91.4
Stratford Ave.	3.30	100.2	100.4	101.1	102.5
Lower Ferry Rd.	3.52	103.8	105.6	106.6	107.5
Carlton Ave.	4.02	112.9	113.6	114.4	114.9
Culvert (Upper Ferry Rd.)	4.89	148.5	145.7(c)	146.1(c)	146.6(c)
Culvert (Scotch Rd.)	5.02	159.7	157.2	157.8	159.0
Reading R.R.	5.04	160.8	159.0	159.4	159.8
Upper Ferry Rd.	5.06	160.3	159.0(d)	159.5(d)	160.0(d)
<u>Little Shabakunk Creek</u>					
Delaware & Raritan Canal Aqueduct	0.03	45.8	52.6	54.2	56.8
U.S. Rte. 1 Northbound (Cul- vert under Construction)	0.32	51.1	52.7	54.3	56.8
U.S. Rte. 1 Southbound & N.J. Rte. 147 (Culvert under Construction)	0.36	51.4	52.9	54.5	56.9
Footbridge	1.31	62.3	62.5	63.2	63.5
Princeton Pike (N.J. Rte. 583)	1.35	62.9	65.5	66.0	67.0
Balsa Dr.	1.68	67.8	70.0	70.1	70.9
Golf Course - Footbridge	1.91	72.0	72.4	72.9	73.8
Golf Course - Footbridge	1.95	72.8	74.9	75.6	76.9

TABLE 6 (Continued)

ELEVATION DATA
Bridges Across Shabakunk, West Branch Shabakunk, and Little Shabakunk Creeks

Identification	Mileage Above Mouth	Under- clearance Elev. (a) Feet-m.s.l.d.	Water Surface Elevation		
			Floodway	Flood Hazard	Standard
			Design Flood(b)	Area Design Flood(b)	Project Flood(b)
			Feet-m.s.l.d.	Feet-m.s.l.d.	Feet-m.s.l.d.
<u>Little Shabakunk Creek</u> (Continued)					
Footbridge (End of Vander Veer Dr.)	1.99	73.4	76.6	77.1	78.2
Private Driveway	2.37	74.9	77.7	78.2	79.3
Private Footbridge	2.46	77.5	80.1	80.5	81.1
Private Footbridge	2.50	78.1	80.6	81.1	81.9
Lawrenceville Rd. (U.S. Rte. 206)	2.54	77.6	81.9	82.4	83.1
Culvert (Rider College Driveway)	3.04	87.6	90.8	91.2	91.7
Footbridge - Rider College	3.08	90.5	90.8	91.2	91.7
Culvert (Rider College Walkway)	3.22	92.2	93.2	93.8	94.4
Culvert (Rider College Driveway)	3.30	93.7	96.6	97.6	98.0
Reading R.R.	3.39	99.6	96.6	97.6	98.0
Culvert (Rider College Driveway)	3.43	93.7	96.6(d)	97.6(d)	98.0(d)
(a) Centerline face of stream. (b) Upstream face of structure. (c) Downstream side of culvert. (d) Downstream side of bridge.					

Table 7 lists average velocities which would occur during peak flows for the Floodway Design Flood, Flood Hazard Area Design Flood, and Standard Project Flood. Generally, the velocities which would occur during a Standard Project Flood are faster because the volume of water which must be carried by the stream is greater than that for a Floodway Design Flood or Flood Hazard Area Design Flood.

Rates of rise and duration - Intense rainfalls that accompany hurricanes usually produce the floods occurring on Shabakunk Creek, West Branch Shabakunk Creek, and Little Shabakunk Creek. The stream channels contain flows for varying time intervals before overbank flooding occurs. Once overbank flooding occurs, the water rises at a rate of about

TABLE 7

MAXIMUM AVERAGE VELOCITIES (a)
Shabakunk, West Branch Shabakunk, and Little Shabakunk Creeks

Location	Mileage Above Mouth	Floodway Design Flood		Flood Hazard Area Design Flood		Standard Project Flood	
		Channel	Overbank (b) Feet per Second	Channel	Overbank (b) Feet per Second	Channel	Overbank (b) Feet per Second
<u>Shabakunk Creek</u>							
Cross Section F	1.56	4.6	0.5	4.6	0.6	4.2	0.6
Downstream of confluence with West Branch Shabakunk Creek	2.18	9.1	0.7	9.3	0.8	7.1	0.8
Cross Section Number:							
4	2.86	8.9	1.2	9.7	2.0	11.2	1.0
8	3.55	4.5	0.4	4.8	0.5	6.2	0.7
13	4.29	2.8	0.3	3.0	0.3	3.8	0.4
20	5.26	3.2	0.6	3.4	0.8	4.1	1.2
27	6.13	5.6	0.6	6.4	0.7	13.3	1.4
<u>West Branch Shabakunk Creek</u>							
12	1.03	4.9	0.8	4.7	0.9	4.6	0.9
23	2.01	3.0	1.1	2.7	1.0	2.4	0.9
25	2.20	3.4	1.2	3.7	1.4	3.7	1.2
<u>Little Shabakunk Creek</u>							
Cross Section Number:							
5	1.05	9.2	1.3	9.5	1.4	10.7	1.7
6	2.03	3.3	0.4	3.5	0.5	3.9	0.5
7	2.93	4.0	0.7	4.3	0.7	4.7	0.8
(a) In reaches unaffected by bridges or other channel constrictions.							
(b) Value given is the greater of the left and right overbank velocity.							

(a) In reaches unaffected by bridges or other channel constrictions.

(b) Value given is the greater of the left and right overbank velocity.

1 to 2 feet per hour. Floodwaters can remain out of banks for time periods up to 1-1/2 days. Table 8 gives the maximum rate of rise (above critical stage), height of rise (from critical stage to maximum flood level), time of rise (time period corresponding to height of rise), and duration of critical stage (period of time flooding is above critical stage level) for the Standard Project Flood at various locations.

TABLE 8
RATES OF RISE AND DURATION
Standard Project Flood

Location	Maximum Rate of Rise <u>Ft./Hr.</u>	Height of Rise <u>Ft.</u>	Time of Rise <u>Hrs.</u>	Duration of Critical Stage <u>Hrs.</u>
<u>Shabakunk Creek</u>				
Between Princeton Pike and Lawrenceville Road	1.8	10.8	13	35
<u>West Branch Shabakunk Creek</u>				
Between Parkside Avenue and Pennington Avenue	1.8	3.3	4	14
<u>Little Shabakunk Creek</u>				
Between Balsam Drive and Lawrenceville Road	1.1	8.1	16	30

Photographs, future flood heights - The levels that the Floodway Design, Flood Hazard Area Design, and Standard Project Floods are expected to reach at various locations along Shabakunk Creek, West Branch Shabakunk Creek, and Little Shabakunk Creek are indicated on the following photographs.




Figure 6 - Future flood heights on Shabakunk Creek at the Westgate Apartments near Lawrenceville Road (U.S. Rte. 206).




Figure 7 - Future flood heights on Shabakunk Creek at the Parkside Avenue bridge.



Figure 8 - Future flood heights on Little Shabakunk Creek at the Princeton Pike bridge (N.J. Rte. 583)



Figure 9 - Future flood heights on West Branch Shabakunk Creek at the Extension Diner near Parkside Avenue.

GLOSSARY

Backwater. The resulting high water surface in a given stream due to a downstream obstruction or high stages in an intersecting stream.

Flood. An overflow of lands not normally covered by water and that are used or usable by man. Floods have two essential characteristics: The inundation of land is temporary; and the land is adjacent to and inundated by overflow from a river, stream, ocean, lake, or other body of standing water.

Normally a "flood" is considered as any temporary rise in streamflow or stage, but not the ponding of surface water, that results in significant adverse effects in the vicinity. Adverse effects may include damages from overflow of land areas, temporary backwater effects in sewers and local drainage channels, creation of unsanitary conditions or other unfavorable situations by deposition of materials in stream channels during flood recessions, rise of ground water coincident with increased streamflow, and other problems.

Flood Crest. The maximum stage or elevation reached by the waters of a flood at a given location.

Flood Hazard Area Design Flood. A flood greater than the Floodway Design Flood that inundates the Floodway and additional portions of the flood plain. This area is known as the Flood Hazard Area. The Floodway (see Floodway Design Flood) is an integral part of the Flood Hazard Area. This flood is also used extensively by the State of New Jersey for planning purposes.

Flood Plain. The areas adjoining a river, stream, watercourse, ocean, lake, or other body of standing water that have been or may be covered by floodwater.

Flood Profile. A graph showing the relationship of water surface elevation to location, the latter generally expressed as distance above mouth for a stream of water flowing in an open channel. It is generally drawn to show surface elevation for the crest of a specific flood, but may be prepared for conditions at a given time or stage.

Flood Stage. The stage or elevation at which overflow of the natural banks of a stream or body of water begins in the reach or area in which the elevation is measured.

Floodway Design Flood. A flood that inundates the channel and portions of the adjacent flood plain necessary for the reasonable passage of flood waters. This area is known as the Floodway and represents the minimum area of the flood plain required for passage of flood waters without aggravating flood conditions upstream or downstream. This flood is used extensively by the State of New Jersey for planning purposes. In the hydrologic region that includes the Shabakunk Creek Watershed, the Floodway Design Flood is equivalent to an event having an average recurrence interval of once in 100 years. (See also: Flood Hazard Area Design Flood).

Hurricane. An intense cyclonic windstorm of tropical origin in which winds tend to spiral inward in a counterclockwise direction toward a core of low pressure, with maximum surface wind velocities that equal or exceed 75 miles per hour (65 knots) for several minutes or longer at some points. Tropical storm is the term applied if maximum winds are less than 75 miles per hour.


Hydrograph. A graph showing flow values against time at a given point, usually measured in cubic feet per second. The area under the curve indicates total volume of flow.


Left Bank. The bank on the left side of a river, stream, or watercourse, looking downstream.


Right Bank. The bank on the right side of a river, stream, or watercourse, looking downstream.

Standard Project Flood. The flood that may be expected from the most severe combination of meteorological and hydrological conditions that are considered reasonably characteristic of the geographical area in which the drainage basin is located, excluding extremely rare combinations. Peak discharges for these floods are generally about 40-60 percent of the Probable Maximum Floods for the same basins. As used by the Corps of Engineers, Standard Project Floods are intended as practicable expressions of the degree of protection that should be sought in the design of flood control works, the failure of which might be disastrous.

Underclearance Elevation. The elevation at the top of the opening of a culvert, or other structure through which water may flow along a water course.







MATCH TO PLATE 4

D

COLONIAL

LAKE



LAKE

C

SHABAKUNK CREEK

FLOW

(SEE NOTES BELOW)

- NOTES:
1. MAPPING NOT PROVIDED FOR THIS AREA
 2. FLOOD HEIGHTS CAN BE OBTAINED FROM PROFILE PLATE 28.

OVERF

N.J.
DESIG
FLOOD

D

CROSS
GROUN
SEA L

NOTES

1. MAPS BASED ON TOPO
MERCER COUNTY, N.J.
2. LIMITS OF OVERFLOW
ACTUAL LOCATION ON
THE REPORT.
3. AREAS OUTSIDE THE
SUBJECT TO FLOODING
4. MINIMUM COUNTOUR

SCA



DEPARTMEN
PHILADELPHIA DISTRICT
PHILADELPHIA

FLOOD PLAT

SHABAKUNK
MERCER
NEW

FLOOD
SHABAKUNK

LEGEND

OVERFLOW LIMITS

N.J. FLOODWAY	STANDARD
DESIGN	PROJECT
FLOOD	FLOOD



CROSS SECTION

GROUND ELEVATION IN FEET
SEA LEVEL DATUM

NOTES

1. MAPS BASED ON TOPOGRAPHIC MAPS SUPPLIED BY MERCER COUNTY, N.J.
2. LIMITS OF OVERFLOW SHOWN MAY VARY FROM ACTUAL LOCATION ON GROUND AS EXPLAINED IN THE REPORT.
3. AREAS OUTSIDE THE FLOOD PLAIN MAY BE SUBJECT TO FLOODING FROM LOCAL RUNOFF.
4. MINIMUM COUNTOUR INTERVAL IS 2 FT.

SCALE IN FEET



DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA

FLOOD PLAIN INFORMATION

SHABAKUNK CREEK
MERCER COUNTY
NEW JERSEY

FLOODED AREAS
SHABAKUNK CREEK

NOT PROVIDED FOR THIS AREA
HEIGHTS CAN BE OBTAINED FROM PROFILE PLATE 28.

MATCH TO PLATE 5


E

SHABAKUNK

M+1

CREEK

FLOW →



STUDY LIMIT

MATCH TO PLATE 3

M + 1

E

NOTES

1. MAPS BASED ON
MERCER COUNTY
2. LIMITS OF ON
ACTUAL LOCAT
THE REPORT.
3. AREAS OUTSIDE
SUBJECT TO I
4. MINIMUM COM

0


DE
PHILADELPHIA
PHIL
FLOI

LEGEND

OVERFLOW LIMITS

N.J. FLOODWAY	STANDARD
DESIGN	PROJECT
FLOOD	FLOOD

M + 1 MILES ABOVE MOUTH

 CROSS SECTION

GROUND ELEVATION IN FEET
SEA LEVEL DATUM

U.S. ROUTE

NOTES

1. MAPS BASED ON TOPOGRAPHIC MAPS SUPPLIED BY MERCER COUNTY, N.J.
2. LIMITS OF OVERFLOW SHOWN MAY VARY FROM ACTUAL LOCATION ON GROUND AS EXPLAINED IN THE REPORT.
3. AREAS OUTSIDE THE FLOOD PLAIN MAY BE SUBJECT TO FLOODING FROM LOCAL RUNOFF.
4. MINIMUM COUNTOUR INTERVAL IS 2 FT.

SCALE IN FEET



DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA


FLOOD PLAIN INFORMATION

SHABAKUNK CREEK
MERCER COUNTY
NEW JERSEY

FLOODED AREAS
SHABAKUNK CREEK

MATCH TO PLATE 6

SHABAKUNK



STUDY

LIMIT

FLOW → CREEK

MATCH TO PLATE 4

F

NOTES

1. MAPS BASED ON MERCER COUNTY.
2. LIMITS OF OVER ACTUAL LOCATIONS THE REPORT.
3. AREAS OUTSIDE SUBJECT TO FLOOD
4. MINIMUM COUNT

0

DEPARTMENT OF
PHILADELPHIA DISTRICT
PHILADELPHIA

FLOOD

SH

FL

SH

FLOW → CREEK

MATCH TO PLATE 4

LEGEND

OVERFLOW LIMITS

N.J. FLOODWAY	STANDARD
DESIGN	PROJECT
FLOOD	FLOOD



CROSS SECTION

GROUND ELEVATION IN FEET
SEA LEVEL DATUM

NOTES

1. MAPS BASED ON TOPOGRAPHIC MAPS SUPPLIED BY MERCER COUNTY, N.J.
2. LIMITS OF OVERFLOW SHOWN MAY VARY FROM ACTUAL LOCATION ON GROUND AS EXPLAINED IN THE REPORT.
3. AREAS OUTSIDE THE FLOOD PLAIN MAY BE SUBJECT TO FLOODING FROM LOCAL RUNOFF.
4. MINIMUM COUNTOUR INTERVAL IS 2 FT.

SCALE IN FEET




DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA

FLOOD PLAIN INFORMATION

SHABAKUNK CREEK
MERCER COUNTY
NEW JERSEY

FLOODED AREAS
SHABAKUNK CREEK

MATCH TO PLATE 7




M + 2

FLOW

STUDY

LIMIT



M+2

2

NOTES

1. MAPS
MERCER
2. LIMITS
ACTUAL
THE
3. AREAS
SUBJE
4. MINIM

MATCH TO PLATE 5

CREEK

FLOW →

M+2

PHILADE

CREEK

MATCH TO PLATE 5

LEGEND

OVERFLOW LIMITS

N.J. FLOODWAY	STANDARD
DESIGN	PROJECT
FLOOD	FLOOD

M+2

MILES ABOVE MOUTH

2 ——— CROSS SECTION


GROUND ELEVATION IN FEET
SEA LEVEL DATUM

U. S. ROUTE

NOTES

1. MAPS BASED ON TOPOGRAPHIC MAPS SUPPLIED BY MERCER COUNTY, N. J
2. LIMITS OF OVERFLOW SHOWN MAY VARY FROM ACTUAL LOCATION ON GROUND AS EXPLAINED IN THE REPORT.
3. AREAS OUTSIDE THE FLOOD PLAIN MAY BE SUBJECT TO FLOODING FROM LOCAL RUNOFF.
4. MINIMUM COUNTOUR INTERVAL IS 2 FT.

SCALE IN FEET



DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA

FLOOD PLAIN INFORMATION

SHABAKUNK CREEK
MERCER COUNTY
NEW JERSEY

FLOODED AREAS
SHABAKUNK CREEK

MATCH TO PLATE 8

M+3

4

SHABAKUNK




M + 3

4

NOTES

1. MAPS BY
MERCER
2. LIMITS
ACTUAL
THE RE
3. AREAS
SUBJECT
4. MINIMUM

PHILADEL



CREEK

MATCH TO
PLATE 6

LEGEND

OVERFLOW LIMITS

}	N. J. FLOODWAY	STANDARD
	DESIGN	PROJECT
	FLOOD	FLOOD

M + 3 MILES ABOVE MOUTH

4 ——— CROSS SECTION

GROUND ELEVATION IN FEET
SEA LEVEL DATUM

NOTES

1. MAPS BASED ON TOPOGRAPHIC MAPS SUPPLIED BY MERCER COUNTY, N. J.
2. LIMITS OF OVERFLOW SHOWN MAY VARY FROM ACTUAL LOCATION ON GROUND AS EXPLAINED IN THE REPORT.
3. AREAS OUTSIDE THE FLOOD PLAIN MAY BE SUBJECT TO FLOODING FROM LOCAL RUNOFF.
4. MINIMUM COUNTOUR INTERVAL IS 2 FT.

SCALE IN FEET



DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA

FLOOD PLAIN INFORMATION

SHABAKUNK CREEK
MERCER COUNTY
NEW JERSEY

FLOODED AREAS
SHABAKUNK CREEK

STUDY LIMIT



MATCH TO PLATE 9


SHABAKUNK

FLOW →

7

5

6



MATCH TO PLATE 7

LEGEND

OVERFLOW LIMITS

{	N.J. FLOODWAY	}	STANDARD
	DESIGN		PROJECT
	FLOOD		FLOOD

6


CROSS SECTION

GROUND ELEVATION IN FEET
SEA LEVEL DATUM

NOTES

1. MAPS BASED ON TOPOGRAPHIC MAPS SUPPLIED BY MERCER COUNTY, N.J.
2. LIMITS OF OVERFLOW SHOWN MAY VARY FROM ACTUAL LOCATION ON GROUND AS EXPLAINED IN THE REPORT.
3. AREAS OUTSIDE THE FLOOD PLAIN MAY BE SUBJECT TO FLOODING FROM LOCAL RUNOFF.
4. MINIMUM COUNTOUR INTERVAL IS 2 FT.

SCALE IN FEET



DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA

FLOOD PLAIN INFORMATION

SHABAKUNK CREEK
MERCER COUNTY
NEW JERSEY

FLOODED AREAS
SHABAKUNK CREEK



MATCH TO PLATE 10

12

SHABAKUNK

11

M+4

10

FLOW →



M + 4

12

MATCH TO PLATE 8

NOTES

1. MAPS B
MERCER
2. LIMITS
ACTUAL
THE RE
3. AREAS
SUBJEC
4. MINIMU

0
6

PHILADELPH

CREEK

9

8

MATCH TO PLATE 8

LEGEND

OVERFLOW LIMITS

N.J. FLOODWAY	STANDARD
DESIGN	PROJECT
FLOOD	FLOOD

M + 4

MILES ABOVE MOUTH

12

CROSS SECTION

GROUND ELEVATION IN FEET
SEA LEVEL DATUM

NOTES

1. MAPS BASED ON TOPOGRAPHIC MAPS SUPPLIED BY MERCER COUNTY, N.J.
2. LIMITS OF OVERFLOW SHOWN MAY VARY FROM ACTUAL LOCATION ON GROUND AS EXPLAINED IN THE REPORT.
3. AREAS OUTSIDE THE FLOOD PLAIN MAY BE SUBJECT TO FLOODING FROM LOCAL RUNOFF.
4. MINIMUM COUNTOUR INTERVAL IS 2 FT.

SCALE IN FEET



DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA

FLOOD PLAIN INFORMATION

SHABAKUNK CREEK
MERCER COUNTY
NEW JERSEY

FLOODED AREAS
SHABAKUNK CREEK

MATCH

TO

STUDY
LIMIT



MATCH TO PLATE 11

14

SHABAKUNK
FLOW →



13

CREEK

MATCH TO PLATE 9


14

NOTES

1. MAPS
MERCER
2. LIMIT
ACTUAL
THE R
3. AREAS
SUBJE
4. MINIM

PHILADEL

SHABAKUNK
Creek
Flow →



LEGEND

OVERFLOW LIMITS

N.J. FLOODWAY	STANDARD
DESIGN	PROJECT
FLOOD	FLOOD


14

CROSS SECTION

GROUND ELEVATION IN FEET
SEA LEVEL DATUM

NOTES

1. MAPS BASED ON TOPOGRAPHIC MAPS SUPPLIED BY MERCER COUNTY, N.J.
2. LIMITS OF OVERFLOW SHOWN MAY VARY FROM ACTUAL LOCATION ON GROUND AS EXPLAINED IN THE REPORT.
3. AREAS OUTSIDE THE FLOOD PLAIN MAY BE SUBJECT TO FLOODING FROM LOCAL RUNOFF.
4. MINIMUM COUNTOUR INTERVAL IS 2 FT.



DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA

FLOOD PLAIN INFORMATION

SHABAKUNK CREEK
MERCER COUNTY
NEW JERSEY

FLOODED AREAS
SHABAKUNK CREEK

MATCH

TO

PLATE 12

M+5

LAKE


SYLVIA

19

17

MATCH

PLATE 12



M
18

NOTES

1. MAP
NER
2. LIM
ACT
THE
3. ARE
SUB
4. MIN

PHILA



15

STUDY
LIMIT

LEGEND

OVERFLOW LIMITS

N.J. FLOODWAY	} STANDARD PROJECT FLOOD
DESIGN	
FLOOD	

M + 5 MILES ABOVE MOUTH

18 ————— CROSS SECTION

GROUND ELEVATION IN FEET
SEA LEVEL DATUM

NOTES

1. MAPS BASED ON TOPOGRAPHIC MAPS SUPPLIED BY MERCER COUNTY, N.J.
2. LIMITS OF OVERFLOW SHOWN MAY VARY FROM ACTUAL LOCATION ON GROUND AS EXPLAINED IN THE REPORT.
3. AREAS OUTSIDE THE FLOOD PLAIN MAY BE SUBJECT TO FLOODING FROM LOCAL RUNOFF.
4. MINIMUM COUNTOUR INTERVAL IS 2 FT.

SCALE IN FEET






DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA

FLOOD PLAIN INFORMATION

SHABAKUNK CREEK
MERCER COUNTY
NEW JERSEY

FLOODED AREAS
SHABAKUNK CREEK





STUDY LIMIT

21

NOTES

- 1. MAI
MEI
- 2. LIN
ACT
THI
- 3. ARI
SUI
- 4. MII

MATCH TO PLATE II

PHIL

LEGEND

OVERFLOW LIMITS

N.J. FLOODWAY	STANDARD
DESIGN	PROJECT
FLOOD	FLOOD

21

CROSS SECTION

GROUND ELEVATION IN FEET
SEA LEVEL DATUM

NOTES

1. MAPS BASED ON TOPOGRAPHIC MAPS SUPPLIED BY MERCER COUNTY, N.J.
2. LIMITS OF OVERFLOW SHOWN MAY VARY FROM ACTUAL LOCATION ON GROUND AS EXPLAINED IN THE REPORT.
3. AREAS OUTSIDE THE FLOOD PLAIN MAY BE SUBJECT TO FLOODING FROM LOCAL RUNOFF.
4. MINIMUM COUNTOUR INTERVAL IS 2 FT.

SCALE IN FEET



TO PLATE II
MATCH

STUDY


LIMIT

DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA


FLOOD PLAIN INFORMATION

SHABAKUNK CREEK
MERCER COUNTY
NEW JERSEY

FLOODED AREAS
SHABAKUNK CREEK



SHABAKUNK



24

NO


1.

2.

3.

4.

PH



LEGEND

OVERFLOW LIMITS

<div> <div></div> <div></div> <div></div> </div>	N.J. FLOODWAY	STANDARD
	DESIGN	PROJECT
	FLOOD	FLOOD

M + 6

MILES ABOVE MOUTH

24


CROSS SECTION

GROUND ELEVATION IN FEET
SEA LEVEL DATUM

NOTES

1. MAPS BASED ON TOPOGRAPHIC MAPS SUPPLIED BY MERCER COUNTY, N.J.
2. LIMITS OF OVERFLOW SHOWN MAY VARY FROM ACTUAL LOCATION ON GROUND AS EXPLAINED IN THE REPORT.
3. AREAS OUTSIDE THE FLOOD PLAIN MAY BE SUBJECT TO FLOODING FROM LOCAL RUNOFF.
4. MINIMUM COUNTOUR INTERVAL IS 2 FT.

SCALE IN FEET





DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA

FLOOD PLAIN INFORMATION

SHABAKUNK CREEK
MERCER COUNTY
NEW JERSEY

FLOODED AREAS
SHABAKUNK CREEK



SHABAKUNK

FLOW

CREEK

2

MATCH TO PLATE 6

LE

OVERFLOW

N. J. F.

DESIGN

FLOOD

6

CROSS

GROUND

SEA LEVEL


NOTES

1. MAPS BASED ON TOPOGRAPHIC MAPS OF MERCER COUNTY, N. J.
2. LIMITS OF OVERFLOW ARE INDICATED BY DASHED LINES. ACTUAL LOCATION ON THE REPORT.
3. AREAS OUTSIDE THE LIMITS OF OVERFLOW ARE SUBJECT TO FLOODING.
4. MINIMUM COUNTOUR IS 100 FEET.

SCALE



DEPARTMENT OF
PHILADELPHIA DISTRICT
PHILADELPHIA
FLOOD PLAN
SHABAKUNK
MERCER COUNTY
NEW JERSEY
FLOOD
WEST BRANCH



LEGEND

OVERFLOW LIMITS

N. J. FLOODWAY	STANDARD
DESIGN	PROJECT
FLOOD	FLOOD

6 CROSS SECTION

GROUND ELEVATION IN FEET
SEA LEVEL DATUM

NOTES

1. MAPS BASED ON TOPOGRAPHIC MAPS SUPPLIED BY MERCER COUNTY, N. J.
2. LIMITS OF OVERFLOW SHOWN MAY VARY FROM ACTUAL LOCATION ON GROUND AS EXPLAINED IN THE REPORT.
3. AREAS OUTSIDE THE FLOOD PLAIN MAY BE SUBJECT TO FLOODING FROM LOCAL RUNOFF.
4. MINIMUM COUNTOUR INTERVAL IS 2 FT.

SCALE IN FEET



DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA

FLOOD PLAIN INFORMATION

SHABAKUNK CREEK
MERCER COUNTY
NEW JERSEY

FLOODED AREAS
WEST BRANCH SHABAKUNK CREEK

MATCH TO PLATE 16

WEST

M + 1

RAILROAD

BRANCH


12


11

10

9

8





CREEK

MATCH TO PLATE 14

LEGEND

OVERFLOW LIMITS

{	N. J. FLOODWAY	STANDARD
	DESIGN	PROJECT
	FLOOD	FLOOD

M + 1 MILES ABOVE MOUTH

8 CROSS SECTION

GROUND ELEVATION IN FEET
SEA LEVEL DATUM

NOTES

1. MAPS BASED ON TOPOGRAPHIC MAPS SUPPLIED BY MERCER COUNTY, N. J.
2. LIMITS OF OVERFLOW SHOWN MAY VARY FROM ACTUAL LOCATION ON GROUND AS EXPLAINED IN THE REPORT.
3. AREAS OUTSIDE THE FLOOD PLAIN MAY BE SUBJECT TO FLOODING FROM LOCAL RUNOFF.
4. MINIMUM COUNTOUR INTERVAL IS 2 FT.

SCALE IN FEET



DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA

FLOOD PLAIN INFORMATION

SHABAKUNK CREEK
MERCER COUNTY
NEW JERSEY

FLOODED AREAS
WEST BRANCH SHABAKUNK CREEK

FLOW →

CREEK

MATCH TO PLATE 14

MATCH TO PLATE 17

WEST

BRANCH


20


19

18

17

16





CREEK

MATCH TO PLATE 15

LEGEND

OVERFLOW LIMITS

N.J. FLOODWAY	STANDARD
DESIGN	PROJECT
FLOOD	FLOOD


15 ——— CROSS SECTION

GROUND ELEVATION IN FEET
SEA LEVEL DATUM

NOTES

1. MAPS BASED ON TOPOGRAPHIC MAPS SUPPLIED BY MERCER COUNTY, N.J.
2. LIMITS OF OVERFLOW SHOWN MAY VARY FROM ACTUAL LOCATION ON GROUND AS EXPLAINED IN THE REPORT.
3. AREAS OUTSIDE THE FLOOD PLAIN MAY BE SUBJECT TO FLOODING FROM LOCAL RUNOFF.
4. MINIMUM COUNTOUR INTERVAL IS 2 FT.

SCALE IN FEET



DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA


FLOOD PLAIN INFORMATION

SHABAKUNK CREEK
— MERCER COUNTY
NEW JERSEY

FLOODED AREAS
WEST BRANCH SHABAKUNK CREEK

MATCH TO PLATE 18

WEST



27

26

25

23

24

BRANCH

FLOW

+2

F/G 8/8

FLOOD PLAIN INFORMATION, SHABAKUNK CREEK, WEST BRANCH SHABAKUNK--ETC(U)
OCT 73

OCT 73

UNCLASSIFIED

DAEN/NAP-82040/FPI40-73/1

NL

2 of 2
AD A
11-8-8

2 of 2
AD A
11-9-8

NO 4
11-8-8


END

DATE _____

0 11 MF C)

9-81

DTIC



24

NO

1

2

3

4

MATCH TO PLATE 16

CREEK

SHABAKUNK


FLOW

DRAINAGE

+2

MAPLE

W. 100' ROAD



LEGEND

OVERFLOW LIMITS

<div> <div></div> <div></div> <div></div> </div>	N.J. FLOODWAY	STANDARD
	DESIGN	PROJECT
	FLOOD	FLOOD

M+2

MILES ABOVE MOUTH

24


CROSS SECTION

GROUND ELEVATION IN FEET
SEA LEVEL DATUM

NOTES

1. MAPS BASED ON TOPOGRAPHIC MAPS SUPPLIED BY MERCER COUNTY, N.J.
2. LIMITS OF OVERFLOW SHOWN MAY VARY FROM ACTUAL LOCATION ON GROUND AS EXPLAINED IN THE REPORT.
3. AREAS OUTSIDE THE FLOOD PLAIN MAY BE SUBJECT TO FLOODING FROM LOCAL RUNOFF.
4. MINIMUM COUNTOUR INTERVAL IS 2 FT.

SCALE IN FEET



DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA


FLOOD PLAIN INFORMATION

SHABAKUNK CREEK
MERCER COUNTY
NEW JERSEY

FLOODED AREAS
WEST BRANCH SHABAKUNK CREEK

MATCH TO PLATE 19

WEST



BRANCH
FLOW →

FOOT
BRIDGE

SHABAKUNK

31

30

N.
 DE
 FL


30 ———— CR
 GE
 SE

NOTES

1. MAPS BASED ON T
MERCER COUNTY,
2. LIMITS OF OVER
ACTUAL LOCATION
THE REPORT.
3. AREAS OUTSIDE T
SUBJECT TO FLOO
4. MINIMUM COUNTS



DEPAR
 PHILADELPHIA DIST
 PHILADEL
 FLOOD P
 SH
 FL
 WEST BRAN



LEGEND

OVERFLOW LIMITS

{	N.J. FLOODWAY	STANDARD
	DESIGN	PROJECT
	FLOOD	FLOOD

30

CROSS SECTION

GROUND ELEVATION IN FEET
SEA LEVEL DATUM

NOTES

1. MAPS BASED ON TOPOGRAPHIC MAPS SUPPLIED BY MERCER COUNTY, N.J.
2. LIMITS OF OVERFLOW SHOWN MAY VARY FROM ACTUAL LOCATION ON GROUND AS EXPLAINED IN THE REPORT.
3. AREAS OUTSIDE THE FLOOD PLAIN MAY BE SUBJECT TO FLOODING FROM LOCAL RUNOFF.
4. MINIMUM COUNTOUR INTERVAL IS 2 FT.

SCALE IN FEET




DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA

FLOOD PLAIN INFORMATION

SHABAKUNK CREEK
MERCER COUNTY
NEW JERSEY

FLOODED AREAS
WEST BRANCH SHABAKUNK CREEK





33

BRANCH

WEST


TO PLATE 20

MATCH

35

36





M + 3

33

NOTES

1. MAPS BASED
MERCER COU
2. LIMITS OF
ACTUAL LOC
THE REPORT
3. AREAS OUTS
SUBJECT TO
4. MINIMUM CO

0

PHILADELPHIA

PHI

FLO

WEST

SHABAKUNK

FLOW →

CREEK

32

M + 3
MATCH TO PLATE 18

LEGEND

OVERFLOW LIMITS

{	N.J. FLOODWAY	}	STANDARD
	DESIGN		PROJECT
	FLOOD		FLOOD

M + 3 MILES ABOVE MOUTH

33

CROSS SECTION

GROUND ELEVATION IN FEET
SEA LEVEL DATUM

NOTES

1. MAPS BASED ON TOPOGRAPHIC MAPS SUPPLIED BY MERCER COUNTY, N.J.
2. LIMITS OF OVERFLOW SHOWN MAY VARY FROM ACTUAL LOCATION ON GROUND AS EXPLAINED IN THE REPORT.
3. AREAS OUTSIDE THE FLOOD PLAIN MAY BE SUBJECT TO FLOODING FROM LOCAL RUNOFF.
4. MINIMUM COUNTOUR INTERVAL IS 2 FT.

SCALE IN FEET





DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA

FLOOD PLAIN INFORMATION


SHABAKUNK CREEK
MERCER COUNTY
NEW JERSEY

FLOODED AREAS
WEST BRANCH SHABAKUNK CREEK





CREEK



MATCH TO PLATE 19

39

NOTES

1. MAP
2. LID
3. ARE
4. MIN

PHILADELPHIA

LEGEND

OVERFLOW LIMITS

{	N.J. FLOODWAY	STANDARD
	DESIGN	PROJECT
	FLOOD	FLOOD

M+4

MILES ABOVE MOUTH

39


CROSS SECTION

GROUND ELEVATION IN FEET
SEA LEVEL DATUM

NOTES

1. MAPS BASED ON TOPOGRAPHIC MAPS SUPPLIED BY MERCER COUNTY, N.J.
2. LIMITS OF OVERFLOW SHOWN MAY VARY FROM ACTUAL LOCATION ON GROUND AS EXPLAINED IN THE REPORT.
3. AREAS OUTSIDE THE FLOOD PLAIN MAY BE SUBJECT TO FLOODING FROM LOCAL RUNOFF.
4. MINIMUM COUNTOUR INTERVAL IS 2 FT.

SCALE IN FEET




DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA

FLOOD PLAIN INFORMATION

SHABAKUNK CREEK
MERCER COUNTY
NEW JERSEY

FLOODED AREAS
WEST BRANCH SHABAKUNK CREEK



LIMIT
STUDY




AREA SUBJECT TO
SHEET FLOW

M45

WEST





STUDY LIMIT

SHABAKUNK

CREEK

STUDY LIMIT

41

MATCH TO PLATE 20

LEGEND

OVERFLOW LIMITS

{	N.J. FLOODWAY	}	STANDARD
	DESIGN		PROJECT
	FLOOD		FLOOD

M+5 MILES ABOVE MOUTH

41


CROSS SECTION

GROUND ELEVATION IN FEET
SEA LEVEL DATUM

NOTES

1. MAPS BASED ON TOPOGRAPHIC MAPS SUPPLIED BY MERCER COUNTY, N.J.
2. LIMITS OF OVERFLOW SHOWN MAY VARY FROM ACTUAL LOCATION ON GROUND AS EXPLAINED IN THE REPORT.
3. AREAS OUTSIDE THE FLOOD PLAIN MAY BE SUBJECT TO FLOODING FROM LOCAL RUNOFF.
4. MINIMUM COUNTOUR INTERVAL IS 2 FT.

SCALE IN FEET





DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA

FLOOD PLAIN INFORMATION

SHABAKUNK CREEK
MERCER COUNTY
NEW JERSEY

FLOODED AREAS
WEST BRANCH SHABAKUNK CREEK

MATCH



LITTLE

SHABAKUNK
FLOW →

(SEE NOTES BELOW)

NOTES:


- 1. MAPP
- 2. FLOO
PROF

CREEK



APPRO
OF CH/

MATCH TO PLATE 23



NOTES:

1. MAPPING NOT PROVIDED FOR THIS AREA.
2. FLOOD HEIGHTS CAN BE OBTAINED FROM PROFILE PLATE 30.

APPROXIMATE RELOCATION
OF CHANNEL

4

NOTES

1. MAPS BASED ON
MERCER COUNTY
2. LIMITS OF
ACTUAL LIMITS
THE REPO
3. AREAS OUT
SUBJECT
4. MINIMUM

PHILADELPHIA

LEGEND

OVERFLOW LIMITS



4

CROSS SECTION

GROUND ELEVATION IN FEET
SEA LEVEL DATUM

U.S. ROUTE

NOTES

1. MAPS BASED ON TOPOGRAPHIC MAPS SUPPLIED BY MERCER COUNTY, N.J.
2. LIMITS OF OVERFLOW SHOWN MAY VARY FROM ACTUAL LOCATION ON GROUND AS EXPLAINED IN THE REPORT.
3. AREAS OUTSIDE THE FLOOD PLAIN MAY BE SUBJECT TO FLOODING FROM LOCAL RUNOFF.
4. MINIMUM COUNTOUR INTERVAL IS 2 FT.

SCALE IN FEET




DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA

FLOOD PLAIN INFORMATION

SHABAKUNK CREEK
MERCER COUNTY
NEW JERSEY

FLOODED AREAS
LITTLE SHABAKUNK CREEK



MATCH TO PLATE 22

MATCH TO PLATE 24


5

M+I

CREEK

SHABAKUNK
← FLOW

STUDY
LIMIT



5

NOTES

1. MA
2. L
3. A
4. M

PHI


MATCH TO PLATE 24

M+1

CREEK

STUDY

LIMIT



LEGEND

OVERFLOW LIMITS

{	N. J. FLOODWAY	}	STANDARD
	DESIGN		PROJECT
	FLOOD		FLOOD

M+1 MILES ABOVE MOUTH


5 CROSS SECTION

GROUND ELEVATION IN FEET
SEA LEVEL DATUM

NOTES

1. MAPS BASED ON TOPOGRAPHIC MAPS SUPPLIED BY MERCER COUNTY, N. J.
2. LIMITS OF OVERFLOW SHOWN MAY VARY FROM ACTUAL LOCATION ON GROUND AS EXPLAINED IN THE REPORT.
3. AREAS OUTSIDE THE FLOOD PLAIN MAY BE SUBJECT TO FLOODING FROM LOCAL RUNOFF.
4. MINIMUM COUNTOUR INTERVAL IS 2 FT.

SCALE IN FEET



DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA


FLOOD PLAIN INFORMATION

SHABAKUNK CREEK
MERCER COUNTY
NEW JERSEY

FLOODED AREAS
LITTLE SHABAKUNK CREEK

STUDY

MATCH TO PLATE 25




LITTLE

SHABAKUNK

DENSE

STUDY

LIMIT



DAM NO. 1


CREEK
FLOW →

MATCH TO PLATE 23

NOTES

1. MAP
2. LIT
3. AR
4. ME

PHI



CREEK
FLOW →

LEGEND

OVERFLOW LIMITS

{	N.J. FLOODWAY	STANDARD
	DESIGN	PROJECT
	FLOOD	FLOOD

GROUND ELEVATION IN FEET
SEA LEVEL DATUM

NOTES

1. MAPS BASED ON TOPOGRAPHIC MAPS SUPPLIED BY MERCER COUNTY, N.J.
2. LIMITS OF OVERFLOW SHOWN MAY VARY FROM ACTUAL LOCATION ON GROUND AS EXPLAINED IN THE REPORT.
3. AREAS OUTSIDE THE FLOOD PLAIN MAY BE SUBJECT TO FLOODING FROM LOCAL RUNOFF.
4. MINIMUM COUNTOUR INTERVAL IS 2 FT.

SCALE IN FEET



DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA

FLOOD PLAIN INFORMATION

SHABAKUNK CREEK
MERCER COUNTY
NEW JERSEY

FLOODED AREAS
LITTLE SHABAKUNK CREEK

MATCH TO PLATE 23

MATCH TO PLATE 26

LITTLE

STUDY

N + 2

SHABAKUN

6

M + 2

6

NOTES

1. MAPS BASED
MERCER CO
2. LIMITS OF
ACTUAL LO
THE REPO
3. AREAS OUT
SUBJECT
4. MINIMUM


MATCH TO PLATE 24

0

PHILADELPH

P

F




STUDY LIMIT

CREEK

FLOW

SHABAKUNK



FLOW →

CREEK

MATCH TO PLATE 24

LEGEND

OVERFLOW LIMITS

}	N. J. FLOODWAY	STANDARD
	DESIGN	PROJECT
	FLOOD	FLOOD

M + 2 MILES ABOVE MOUTH

6 CROSS SECTION

GROUND ELEVATION IN FEET
SEA LEVEL DATUM

NOTES

1. MAPS BASED ON TOPOGRAPHIC MAPS SUPPLIED BY MERCER COUNTY, N. J.
2. LIMITS OF OVERFLOW SHOWN MAY VARY FROM ACTUAL LOCATION ON GROUND AS EXPLAINED IN THE REPORT.
3. AREAS OUTSIDE THE FLOOD PLAIN MAY BE SUBJECT TO FLOODING FROM LOCAL RUNOFF.
4. MINIMUM COUNTOUR INTERVAL IS 2 FT

SCALE IN FEET



DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA

FLOOD PLAIN INFORMATION

SHABAKUNK CREEK
MERCER COUNTY
NEW JERSEY

FLOODED AREAS
LITTLE SHABAKUNK CREEK

MATCH TO PLATE 25

MATCH TO PLATE 27

LITTLE

SHABAKUNK

CREEK

STUDY

LIMIT

MATCH TO PLATE 25


CREEK


DAM NO. 2

FLOW

OOT

LIMIT





LEGEND

OVERFLOW LIMITS

N. J. FLOODWAY	} STANDARD PROJECT FLOOD
DESIGN	
FLOOD	

GROUND ELEVATION IN FEET
SEA LEVEL DATUM




U.S. ROUTE

NOTES

1. MAPS BASED ON TOPOGRAPHIC MAPS SUPPLIED BY MERCER COUNTY, N.J.
2. LIMITS OF OVERFLOW SHOWN MAY VARY FROM ACTUAL LOCATION ON GROUND AS EXPLAINED IN THE REPORT.
3. AREAS OUTSIDE THE FLOOD PLAIN MAY BE SUBJECT TO FLOODING FROM LOCAL RUNOFF.
4. MINIMUM COUNTOUR INTERVAL IS 2 FT.

SCALE IN FEET



DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA

FLOOD PLAIN INFORMATION

SHABAKUNK CREEK
MERCER COUNTY
NEW JERSEY

FLOODED AREAS
LITTLE SHABAKUNK CREEK

STUDY

LIMIT

LITTLE

8

CENTENNIAL
LAKE

CENTENNIAL
LAKE

SHABAKUNK

M+3

FLOW →

STUDY

LIMIT

CREEK

7

M+3

8

NOTES


1. MAPS BAS
MERCER C
2. LIMITS O
ACTUAL L
THE REPO
3. AREAS ON
SUBJECT
4. MINIMUM

MATCH TO PLATE 26

PHILADELPHI

I

F



MATCH TO PLATE 26

LEGEND

OVERFLOW LIMITS

<div> <div></div> <div></div> <div></div> </div>	N. J. FLOODWAY	STANDARD
	DESIGN	PROJECT
	FLOOD	FLOOD

M+3 MILES ABOVE MOUTH

8 CROSS SECTION

GROUND ELEVATION IN FEET
SEA LEVEL DATUM

RGL

NOTES

1. MAPS BASED ON TOPOGRAPHIC MAPS SUPPLIED BY MERCER COUNTY, N. J.
2. LIMITS OF OVERFLOW SHOWN MAY VARY FROM ACTUAL LOCATION ON GROUND AS EXPLAINED IN THE REPORT.
3. AREAS OUTSIDE THE FLOOD PLAIN MAY BE SUBJECT TO FLOODING FROM LOCAL RUNOFF.
4. MINIMUM COUNTOUR INTERVAL IS 2 FT.

SCALE IN FEET





DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA

FLOOD PLAIN INFORMATION


SHABAKUNK CREEK
MERCER COUNTY
NEW JERSEY


FLOODED AREAS
LITTLE SHABAKUNK CREEK









MILES ABOVE CONFLUENCE WITH ASSUNPINK CREEK

























NOTES:

Eight sections surveyed by
Philadelphia District, Corps of
Engineers Personnel.

Cross sections taken
looking downstream.




LEGEND

- Standard Project Flood
- N.J. Flood Hazard Area Design Flood
- N.J. Floodway Design Flood

HORIZONTAL DISTANCE IN HUNDREDS OF FEET

DEPARTMENT OF THE ARMY
PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
PHILADELPHIA, PENNSYLVANIA
FLOOD PLAIN INFORMATION
SHABAKUNK CREEK
MERCER COUNTY, N.J.
SELECTED CROSS SECTIONS
LITTLE SHABAKUNK CREEK



NOTES

<u>DRAINAGE AREA</u>	<u>SQ. MI.</u>
SHABAKUNK CREEK- DOWNSTREAM OF CONFLUENCE WITH WEST BRANCH	10.8
WEST BRANCH SHABAKUNK CREEK- AT PENNINGTON AVENUE	3.3
LITTLE SHABAKUNK CREEK- DOWNSTREAM OF LAWRENCEVILLE ROAD	2.2

DEPARTMENT OF THE ARMY
 PHILADELPHIA DISTRICT, CORPS OF ENGINEERS
 PHILADELPHIA, PENNSYLVANIA
 FLOOD PLAIN INFORMATION
 SHABAKUNK CREEK
 MERCER COUNTY, N.J.
 STANDARD PROJECT FLOOD
 HYDROGRAPHS

DATE
FILMED
-8